



**1ST FLOOR FRAMING & UPPER FOUNDATION PLAN**

3/16"=1'-0"

**NOTES:**

- INDICATES SPAN DIRECTION OF 3 1/2" NORMAL WEIGHT CONCRETE SLAB ON 2VL120GA GALV METAL DECK (3 1/2" CONCRETE FILL OVER 2" DECK, 5 1/2" TOTAL, 3 SPAN MIN), W/W6x6-W2.1xW2.1 W.W.F.
- TOP OF SLAB EL. 100'-0" U.N.O.
- TOP OF STEEL EL. 99'-6 1/2" U.N.O.
- [XX] INDICATES 3/4"x3 1/2" LG HEADED SHEAR STUDS UNIFORMLY SPACED ALONG W BEAM SPAN OR BETWEEN CONCENTRATED LOADS. (MAX SPACING 18").
- INDICATES MOMENT CONN. SEE TYP DETAIL DWG S3.1
- BF-X INDICATES VERTICAL BRACING. SEE BRACING ELEVATIONS DWG S1.8
- BEAMS ARE EQUALLY SPACED WITHIN BAYS U.N.O.
- \*\*\* INDICATES DIMENSION TO BE VERIFIED W/APPROVED MECHANIZED PARKING SUBMITTAL.

| FOOTING SCHEDULE |                   |                           |
|------------------|-------------------|---------------------------|
| FOOTING MARK     | FOOTING SIZE      | REINF EACH WAY BOT U.N.O. |
| F3               | 3'-0"x3'-0"x1'-0" | 3#5                       |
| F4               | 4'-0"x4'-0"x1'-0" | 4#5                       |
| F5               | 5'-0"x5'-0"x1'-2" | 5#5                       |
| F6               | 6'-0"x6'-0"x1'-4" | 6#6                       |
| CF-1             | 6'-6"x4'-0"x1'-4" | 6#6                       |



**PERMIT SET**

DRAFTSPERSON: [Blank]  
DATE OF ISSUE: 07/21/19  
PROJECT STATUS: [Blank]

221 Congress Street  
Hay Runner, LLC  
221 Congress Street Portland ME 04101