



© 2014 RYAN SENATORE ARCHITECTURE

**RESTAURANT FIT-UP**  
 75 WASHINGTON AVENUE  
 PORTLAND, MAINE



RYAN SENATORE  
 ARCHITECTURE  
 565 CONGRESS STREET  
 SUITE 304  
 PORTLAND, MAINE 04101  
 207-650-6414  
 senatorearchitecture.com

CONSULTANTS:

REVISIONS:

DATE: OCTOBER 17, 2014

PROJECT No.

DRAWN BY:

CHECKED BY: RJS

SCALE: AS NOTED

SHEET TITLE:  
**FINISH  
 SCHEDULE**

**A7-1**

**ROOM FINISH SCHEDULE**

ROOM #	ROOM NAME	WALLS					FLOOR	CEILINGS			REMARKS	PAINT COLOR
		NORTH	EAST	SOUTH	WEST	BASE		MATL.	HEIGHT	RATING		
100	VESTIBULE	1	1	1	1	11	22	33	-	1 HR		
101	RESTAURANT	1	1	4	1	11	22	33	-	1 HR		
102	GROUP DINING ROOM	1	1	1	1	11	21	31	-	1 HR		
103	KITCHEN	5,2	5,2	5,2	5,2	10	23	32	-	1 HR		
104	BAR	-	-	4	-	10	20	33	-	1 HR		
105	HALLWAY	1	1	1	-	11	22	33	-	1 HR		
106	MEN'S TOILET	6,7	6,7	4	6,7	13	20	31	-	1 HR		
107	WOMEN'S TOILET	6,7	6,7	4	6,7	13	20	31	-	1 HR		
108	RESTAURANT PREP	5,8	5,8	5,8	5,8	12	24	32	-	1 HR		
109	DRY GOODS STORAGE	1	1	1	1	12	24	33	-	1 HR		

**FINISH SCHEDULE KEY**

WALLS	
1	GWB - PAINTED
2	FRP TO 8'-0" AFF. - EPOXY PAINTED GWB TO CEILING
3	MOISTURE RESISTANT GWB - PAINTED
4	BRICK - PAINTED
5	EPOXY PAINT
6	WALL PAPER
7	SUBWAY TILE TO 48" AFF. WITH BULLNOSE CAP
8	FRP TO 4'-0" AFF. - EPOXY PAINTED GWB TO CEILING
BASE	
10	6" QUARRY TILE BASE
11	1X4 WOOD BASE
12	4" VINYL COVE BASE
13	SUBWAY TILE COVE BASE
FLOORS	
20	QUARRY TILE - COLOR #1
21	SHEET VINYL
22	REMOVE EXISTING TILE - CLEAN PATCH AND REPAIR CONCRETE APPLY STAINED FINISH
23	QUARRY TILE - COLOR #2
24	NEW CONCRETE SLAB - PAINT AND SEAL
25	
26	
27	
28	
CEILINGS	
30	GWB - PAINTED
31	2' X 2' ACOUSTICAL HUNG CEILING TILES - ARMSTRONG CIRBUS # 578 FIREGUARD
32	2' X 2' ACOUSTICAL HUNG CEILING TILES - ARMSTRONG CLEAN ROOM VL # 868 FIREGUARD
33	PAINTED 1HR FIREPROOFING
34	

**ROOM FINISH GENERAL NOTES**

- 1 ALSO SEE INTERIOR ELEVATIONS FOR GRAPHIC DEPICTIONS OF EXTENT OF FINISHES
- 2 INSTALL MOISTURE RESISTANT (MOLD AND MILDEW RESISTANT) GWB IN ALL AREAS WHERE PLUMBING FIXTURES EXIST (CEILING AND WALLS IN BATHROOMS)
- 3 CLOSETS SHALL BE FINISHED AS THE ROOMS THEY SERVICE
- 4 ALL SPACES DESIGNATED AS CLOSET OR 'CL.' ARE TO RECEIVE ONE CLOTHING ROD 5'-2" AFF AND ONE 12" SHELF ABOVE THE ROD ALONG THE WALL OPPOSITE THE DOOR UNLESS NOTED OTHERWISE.
- 5 ALL SPACES DESIGNATED AS LINEN CLOSETS (LIN) OR PANTRY (PAN) ARE TO RECEIVE FOUR 12" SHELVES SPACED AT 1'-6" OC STARTING AT FINISH FLOOR. UNLESS NOTED OTHERWISE.
- 6 PROVIDE APPROPRIATE BLOCKING IN WALLS OF ALL BATHROOMS BEHIND FIXTURES, PARTITIONS AND ACCESSORIES. PROVIDE BLOCKING FOR GRAB BARS IN WALLS OF BATHROOMS
- 7 PROVIDE APPROPRIATE BLOCKING IN WALLS FOR DOOR STOPS
- 8 PROVIDE APPROPRIATE BLOCKING IN WALLS FOR WALL HUNG CABINETS
- 8 BOTTOM EDGE OF GWB ON WALL SURFACES TO BE HELD UP 1/2" FROM CONCRETE FLOOR SURFACES
- 9 PROVIDE VINYL TRANSITIONS STRIPS AT ALL FLOOR TRANSITIONS UNLESS OTHERWISE NOTED
- 10 UNLESS OTHERWISE NOTED IN DRAWINGS THE TYPICAL WALL TYPE IS 'NA'. ALL OTHER PARTITION TYPES WILL BE INDICATED.
- 11 VERIFY UNDERLAYMENT MEETS MANUFACTURERS SPECIFICATION AT RESILIENT FLOORING

**PAINT NOTES**

- 1.) TBD
- 2.)
- 3.)