



Please Note:  
 Additional Exit Sign to be added in the middle  
 of the space should line of sight be obstructed  
 from any part of the tenant space

IN TOTAL:  
 2 EXIT SIGNS OVER EACH DOOR  
 6 EMERGENCY LIGHTS  
 ALL ENERGIZED VIA LIGHTING CIRCUIT  
 PER LOCAL AND NATIONAL CODE

Exit/Emergency  
 Combo

Receptacles spaced at 12' per code

4 Emergency lights  
 rated for minimum of  
 90 minutes to provide  
 a minimum of .1 foot  
 candles per NFPA  
 101 Life Safety Code  
 2006,section 7.9

*4' LED indirect suspended lights controlled  
 via 3-way switch at either door. 0-10volt dimming*

Exit/Emergency  
 Combo