

Code Review				Oct 21, 2015
-------------	--	--	--	--------------

## Interior Renovations at the Nissen Building Suite 1E - Distillery

	IBC 2009		NFPA 101 2009	
Sprinklers		NFPA 13		NFPA 13
Occupant Load	T 1004.1.1	Industrial = 3,834 sf (100 gsf/oc) = 39  <b>Total Occupant Load = 39</b>	7.3.1.2	Industrial = 3,834 sf (100 gsf/oc) = 39  <b>Total Occupant Load = 39</b>
Use Group(s)	306.2	Factory F-1 Moderate Hazard  Retail use is under 10% of area and thus Accessory use	40.1	Industrial - General Hazard
Construction Type	T 503	3B - mixed combustible unprotected		III-N mixed combustible unprotected
	1016.1	250' Travel Distance to exits with Sprinklers	40.2.6	250' Travel distance to exit
	1014.3	100' Common Path of Travel	40.2.5	100' Common Path of Travel
	1018.4	50' Dead End	40.2.5	50' Dead End
Egress Corridors	1018.2	36" min. when Occ. <= 50	7.2.2.2.1.2	36" min. when Occ. <= 50
Separations	508.4	F-1 and adjacent S-2 = 1hr with sprinkler	6.1.14.1	Industrial and Storage = 1hr
	508.2.5	Boiler room 1hr		