Reviewed for Code Compliance
Inspection Division
Portland, Maine
Date: 01/07/16

NOTES:
1. EXTERIOR DOOR JAMBS TO BE SEALED TO THIER ROUGH OPENINGS USING LOW EXPANDING FOAM, BACKER ROD OR CAULKING.
2. ALL EXTERIOR DOORS TO BE WEATHER STRIPPED

GLAZING SCHEDULE

KEY	GLAZING TYPE
GL-1	INSULATED CLEAR GLAZING
GL-2	FIRE RATED INSULATED GLAZING
GL-3	CLEAR TEMPERED GLASS
GL-4	CLEAR INSULATED TEMPERED GLASS
GL-5	FIRE RATED GLAZING

1 DOOR TYPES
1/4" = 1'-0"

LEGEND:
T = TEMPERED GLASS
F = FIXED

NOTES:
1. CONTRACTOR TO VERIFY ALL ROUGH OPENINGS
2. ALL EXTERIOR GLAZING INSULATED
3. FRAME OPENINGS WITH ELEVATIONS
4. SEAL WINDOW TO ROUGH OPENINGS WITH LOW EXPANDING FOAM
INSULATION - SEE DETAILS

2 WINDOW TYPES
1/4" = 1'-0"

WINDOW SCHEDULE

KEY	ACTION	ROUGH ★ OPENING (WxH) VIF	R.O.TO HEAD HEIGHT FROM FINISH FLOOR	DETAILS HEAD	DETAILS JAMB	DETAILS SILL	MATERIAL	FINISH	FOR TEMPERED GLASS LOCATIONS SEE WINDOW ELEVATION TYPES FOR MASONRY OPENING DIMENSIONS COORDINATE COURSING WITH EXTERIOR ELEVATION SHEETS AND PLAN AND SECTION DETAIL SHEETS REMARKS
A	STORE	5'-6" X 12'-10"	-	-	-	-	AL	ANO	OLDCASTLE SERIES 3000 THERMAL MULTIPANE CENTER SET - THERMALLY BROKEN STOREFRONT WINDOW SYSTEM - PROVIDE STEEL REINFORCING WITHIN MEMBERS
B	F	-	-	-	-	-	VL	-	FIXED WINDOW AT PENHOUSE SOUTH WALL, SEE SECTION DETAIL FOR WINDOW INFOMATION

DOOR SCHEDULE

DOOR NO.	TYPE	SIZE WIDTH	SIZE HEIGHT	SIZE THICKNESS	DOOR MATERIAL	DOOR FINISH	INSULATED	FRAME TYPE	FRAME MATERIAL	THRESHOLD	DETAILS HEAD	DETAILS JAMB	DETAILS SILL	CLOSER	FIRE RATING (MINUTES)	HARDWARE	REMARKS
100.1	E	14'-0"	12'-10"	1-3/4"	AL	ANO	Y	-	AL		-	-	-	Y	-	-	OVERHEAD DOOR WITH AUTOMATIC OPERATOR, BY OVERHEAD DOOR, 521 SERIES, FINISH TO MATCH ADJACENT STOREFRONT
100.2	A	3'-0"	7'-0"	1-3/4"	AL	ANO	Y	-	AL	AL	-	-	-	Y	-	-	STOREFRONT DOOR WITH PANIC HARDWARE
100.3	D	3'-0"	7'-0"	1-3/4"	STL	PTD	-	-	STL	-	-	-	-	-	-	-	NEW DOOR IN EXISTING OPENING, MODIFY OPENING AS REQUIRED
102.1	C	3'-0"	7'-0"	1-3/4"	STL	PTD	Y	1	STL	AL	-	-	-	Y	60	-	FIRE DOOR WITH PANIC HARDWARE
103.1	B	3'-0"	7'-0"	1-3/4"	STL	PTD	Y	1	STL	-	-	-	-	Y	-	-	
104.1	C	3'-0"	7'-0"	1-3/4"	STL	PTD	Y	1	STL	AL	-	-	-	Y	60	-	FIRE DOOR WITH PANIC HARDWARE
105.1	C	3'-0"	7'-0"	1-3/4"	STL	PTD	Y	1	STL	AL	-	-	-	Y	60	-	FIRE DOOR WITH PANIC HARDWARE
105.2	C	3'-0"	6'-8"	1-3/4"	STL	PTD	Y	1	STL	AL	-	-	-	Y	60	-	FIRE DOOR WITH PANIC HARDWARE

HARDWARE KEY
M.S - MORTISE LOCK SET
L.S - LOCK SET
PR - PRIVACY SET
PS - PASSAGE SET
LP - LEVER PULL
PH - PEEPHOLE LENSE

ABBREVIATION KEY
STL - STEEL
WD - WOOD
AL - ALUMINUM
ANO - ANNODIZED
PTD - PAINTED
STR - STOREFRONT

STOREFRONT INFORMATION

1.) ALL STOREFRONT TO BE THERMALLY BROKEN WITH INSULATED GLAZING UNITS WITH LOW-E COATING ARGON FILLED UNITS

2.) TEMPER ALL GLASS AS REQUIRED BY BUILDING CODE

3.) PROVIDE SUB SILLS WITH DRAINED PANS WITH END AND BACK DAMS, PROVIDE COMPRESSION HEAD SLIP TRACKS

4.) PROVIDE FINISH TO MATCH ADJACENT EXISTING STOREFRONT, PROVIDE SAMPLE AND SHOP DRAWINGS FOR OWNER AND ARCHITECT APPROVAL PRIOR TO ORDER

5.) FOR STOREFRONT FRAME GEOMETRY AND ARRANGEMENTS SEE EXTERIOR BUILDING ELEVATIONS

6.) G.C. TO FIELD MEASURE ALL STOREFRONT UNITS PRIOR TO ORDER

7.) PROVIDE STANDARD HEAD COMPENSATING RECEPTORS (DEFLECTION HEAD)

REGISTERED ARCHITECT
RYAN J. SENATORE
No. 3322
STATE OF MAINE

© 2015 RYAN SENATORE ARCHITECTURE

NISSEN BUILDING
RENOVATIONS
PORTLAND, MAINE

RSA
RYAN SENATORE
ARCHITECTURE
565 CONGRESS STREET
PORTLAND, MAINE
207-650-6414
senatorearchitecture.com

CONSULTANTS:
STRUCTURAL:
Structural Integrity
77 Oak Street
Portland, ME 04101
207-774-4614

REVISIONS:

DATE:	NOVEMBER 9, 2015
PROJECT No.	1523
DRAWN BY:	JPF
CHECKED BY:	RJS
SCALE:	AS NOTED

SHEET TITLE:
DOOR AND WINDOW SCHEDULE

A7-0