

Code Review		Jan 7, 2016		
Interior Renovations at the Nissen Building Suite 1C				
	IBC 2009			NFPA 101 2009
Sprinklers		NFPA 13		NFPA 13
Occupant Load	T 1004.1.1	Mercantile = 681 sf (30 gsf/oc) = 23 Assembly Tables and Chairs = 524 sf (15 nsf/oc) = 35 Total Occupant Load = 58	7.3.1.2	Mercantile = 681 sf (30 gsf/oc) = 23 Assembly Tables and Chairs = 524 sf (15 nsf/oc) = 35 Total Occupant Load = 58
Use Group(s)	306.2	M - Mercantile	36.1	Mercantile
		A2 - Restaurant	12.1	Assembly
Construction Type	T 503	3B - mixed combustible unprotected		III-N mixed combustible unprotected
	1016.1	250' Travel Distance to exits with Sprinklers	12.2.6.2	250' Travel distance to exit
	1014.3	As part of MUBEC CH. 3 table 1014.3 in IBC 2009 was deleted and table A7.6 in NFPA was Added	12.2.5.1.2	75' Common Path of Travel
	1018.4	20' Dead End	12.2.5	20' Dead End
Egress Corridors	1018.2	44" min. when Occ. > 50	12.2.3.8	44" min. when Occ. > 50
Separations	508.3	Non Separated Occupancies	6.1.14.3	Non Separated Occupancies

Interior Renovations at the Nissen Building Suite 1C