



Install Date: 8/12/15
75 Washington Ave
75 Washington Ave
Portland, ME 04101
Cintas Fire Protection
603-717-7300

Cintas Fire Protection
3 Tallwood Drive
Bow, NH 03304
John Quinn
603-717-7300
quinnj@cintas.com
4982

Notes

Fusible Links:

=> To determine actual fusible link ratings, temperature readings must be taken during peak cooking time.

75 Washington Ave:

Note 1 => Nozzle: 1F x 3: (Range: 6 burners) nozzle position: 40-48 in., front edge of burner, nozzle flats parallel with burner front-to-rear centerline, aimed at center

Note 2 => Nozzle: 1N x 1: (undefined) nozzle position: Directly in line with either vertical edge of broiler opening, 6-12 in. in front of opening, and 0-12 in. above top of broiler, aimed at center of opening.