



4x6 p.t. beam fasten to post w/ Simpson BC4Z

2x6 p.t. rafter @ 16" o.c. fasten to beam w/ Simpson A35

1x6 t&g sheathing fasten to rafters w/ 8d galv. nails

4x6 p.t beam fasten to post w/ Simpson ABA 44Z

Existing 5x5 cedar post and fence

4x4 p.t. post

Grade

4x4 p.t. post min. 48 in. below grade

12"x12"x4" poured concrete footing

116 Sheridan Street
Framing Detail
Storage Shed