

1 NORTH ELEVATION
1/4" = 1'-0"



2 EAST ELEVATION
1/4" = 1'-0"

GENERAL NOTES:

1. FLOOR ELEVATION 0'-0" CORRESPONDS TO SURVEY ELEVATION 121'-0"

2. PAINT METAL VENT COVERS TO MATCH SIDING.

3. VENTS CENTERED ON SIDING AS SHOWN ON ELEVATIONS

WINDOW SCHEDULE

Type	Width	Height	Count	Operation	Notes	U-FACTOR	SHGC
A	3' - 2"	4' - 9"	5	CASEMENT	MEETS EGRESS REQUIREMENTS	0.18	0.39
A1	3' - 2"	4' - 9"	1	FIXED		0.17	0.47
B	6' - 0"	4' - 9"	1	FIXED		0.17	0.47
C	6' - 0"	5' - 0"	1	FIXED/CASEMENT	MEETS EGRESS REQUIREMENTS	0.17/0.18	0.46/0.39
D	6' - 0"	6' - 3"	1	FIXED/CASEMENT		0.17/0.46	0.46/0.39
E	7' - 0"	4' - 9"	2	CASEMENT/FIXED	MEETS EGRESS REQUIREMENTS	0.18/0.17	0.39/0.46
F	4' - 0"	4' - 9"	2	FIXED		0.17	0.47
G	2' - 6"	4' - 9"	4	CASEMENT	MEETS EGRESS REQUIREMENTS	0.18	0.39
H	7' - 0"	6' - 3"	2	CASEMENT/FIXED		0.18/0.17	0.39/0.46
I	3' - 0"	6' - 3"	2	FIXED		0.17	0.47
J	6' - 0"	4' - 9"	1	CASEMENT/FIXED	MEETS EGRESS REQUIREMENTS	0.18/0.17	0.39/0.46
J1	6' - 0"	4' - 9"	1	FIXED/CASEMENT	MEETS EGRESS REQUIREMENTS	0.17/0.18	0.46/0.39
K	7' - 9"	4' - 9"	1	CASEMENT/FIXED	MEETS EGRESS REQUIREMENTS	0.18/0.17	0.39/0.46
L	5' - 0"	2' - 3"	2	AWNING		0.18	0.39
L1	5' - 0"	2' - 3"	2	FIXED		0.17	0.47
M	3' - 6"	6' - 6"	2	FIXED		0.17	0.47
S	1' - 6"	7' - 0"	1	FIXED	ENTRY DOOR SIDELIGHT	0.18	0.39

GENERAL NOTES:

1. WINDOWS BY KOHLTECH
2. DARK BRONZE EXTERIOR COLOR. WHITE INTERIOR
3. ALL GLASS TO BE TEMPERED AS REQUIRE BY CODE
4. PROVIDE SCREENS ON ALL OPERABLE UNITS



WINDOW LEGEND
1/4" = 1'-0"



D1 INSULATED ENTRY DOOR & SIDELIGHT

D2 FLUSH STEEL INSULATED ENTRY DOOR

D3 INSULATED FULL LIGHT ENTRY DOOR BY WINDOW MANUF.

D4 HAMMEL BY MASONITE, HINGED OR POCKET

D5 HAMMEL BY MASONITE, BYPASS

D6 MASONITE FLUSH DOOR, BIFOLD

D7 HAMMEL BY MASONITE, DOUBLE SLIDING/STACKING

D8 CUSTOM CABINET DOOR

D9 OVERHEAD GARAGE DOOR

DOOR LEGEND
1/4" = 1'-0"

DOOR SCHEDULE

Mark	Type	Width	Height	Operation	Hardware	Comments
101A	D1	3' - 0"	7' - 0"	EXTERIOR SWING		
101B	D4	3' - 0"	7' - 0"	SWING		
101C	D2	3' - 0"	7' - 0"	SWING		PAINT TO MATCH WALL COLOR
102A	H	17' - 6"	8' - 0"	OVERHEAD GARAGE		18'-0" M.O., VERIFY SIZE OF DOOR WITH MANUFACTURER
102B	D12	3' - 0"	8' - 0"			
102C	D2	3' - 0"	7' - 0"	SWING		
103	D4	2' - 6"	7' - 0"	SWING		
104	D5	5' - 0"	7' - 0"	TWO PANEL BYPASS		
202A	D4	3' - 0"	7' - 0"	SWING		
202B	D4	2' - 6"	7' - 0"	POCKET		
203	D4	3' - 0"	7' - 0"	POCKET		
204	D4	3' - 0"	7' - 0"	POCKET		
205	D4	3' - 0"	7' - 0"	POCKET		
207	D4	3' - 0"	7' - 0"	POCKET		
208A	D4	3' - 0"	7' - 0"	POCKET		
208B	D4	2' - 6"	7' - 0"	SWING		
209	D4	3' - 0"	7' - 0"	POCKET		
210	D5	5' - 0"	7' - 0"	BIFOLD		
300	D8	0' - 10"	7' - 0"	SWING		
301	D4	2' - 6"	7' - 0"	POCKET		
302	D3	3' - 6"	8' - 0"	EXTERIOR SWING		
304	D11	2' - 0"	7' - 0"			
305	D4	2' - 6"	7' - 0"	POCKET		
306A	D4	3' - 0"	7' - 0"	SWING		
306B	D7	5' - 3"	7' - 0"	DOUBLE SLIDING/STACKING		



3 TYPICAL STANDING SEAM CORNER DETAIL
1 1/2" = 1'-0"

LICENSED ARCHITECT HARRY W. HEPBURN IV No. 3338 STATE OF MAINE

Expiration Date: 11/20/14

BOGG + KIEFNER RESIDENCE
100 SHERIDAN STREET, PORTLAND, MAINE

BR BURN architecture for life
5 Maple St., Suite 202 | Portland, ME 04101 | 207-774-4662

CONSULTANTS:

REVISIONS:
RE-ISSUED 10/27/14

ISSUED:	09/30/14
PROJECT No:	1410
DRAWN BY:	LB
CHECKED BY:	HWH

SHEET TITLE:
EXTERIOR ELEVATIONS

A201