Main Line Fence

207
800
ww
FA
Mai
272
Cumberland, Maine 04021

Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 04/29/16

Nancy Bogg
98 Sheridan St.
Portland, ME 04101

March 2, 2016

We propose to furnish materials and labor necessary to install approximately 30 lineal feet of 28" High Wood Guard Rail with Corten Steel Posts. Posts are to be welded to plates and bolted to concrete using galvanized concrete wedge anchors. Guard Rail Beam is to be a 3x10 Pressure Treated Rail bolted to posts with countersunk galvanized bolts.

Lump Sum Price $1,200.00

Terms: 25% deposit with order, balance due within 30 days after completion.

Main Line Fence Co. assumes no responsibility for any damage to underground pipes, power lines, etc. in the process of installing posts, if the company is not notified of existence of same in writing. Customer assumes all responsibility for location of property lines; Main Line Fence Co. is not responsible for costs associated with moving or removing fences where the property lines have not been properly located before the installation.

We are fully insured for Worker's Compensation, Public Liability, and Property Damage. Certificates will be forwarded upon request.

Please print, sign and return a copy of this contract. If this proposal is not covered by a purchase order within 30 days it may be necessary to renegotiate same.

Accepted: Main Line Fence Co.

By:_____ Ryan Cianchette

Amount Enclosed:
$_____