

Dependable Hood & Duct Cleaning Company, LLC

424 Old Candia Road - Unit 1 Candia, NH 03034

603-483-0199

www.nhhoodcleaning.com
Service@dependablehood.com

Account :	Hilltop Superette	Date of Service :	05/08/2023
Location :	Hilltop Superette	Frequency :	180 days
Loc.Add :	135 Congress St, Portland, ME 04101 Portland, Maine 04101	Tech Name:	Christopher Morlock - HC-000778 - 11/29/25
Date :	05/18/2023		
Phone :	(207) 773-8000		

Service	Options	Comments
1. Are the filters clean?	Yes	FilterShine exchange service
2. Do any filters need replacement?	No	
3. Is the grease load less than 2000 microns: (Horizontal)	Yes	
4. Is the grease load less than 2000 microns: (Vertical)	Yes	
5. Is the grease load less than 2000 microns: (Hood)	Yes	
6. Is the fan grease load less than 3175 microns?	Yes	
7. Last cleaning/inspection date:	5/8/2023	1st cleaning with Dependable Hood and Duct Cleaning Co.
8. Did you clean or inspect the systems?	Cleaned/Inspected	
9. Was a Certificate of Performance placed on the hood?	Yes	White tags SN#000822, 000823
10. If a wash system, is the main valve in the open position?	N/A	
11. Are all filters in place?	Yes	
12. Do the fans operate?	Yes	
13. Have the duct dampers been cleaned/inspected?	N/A	
14. Were the exhaust fans cleaned?	Yes	A hinge kit was installed on the mainline system and access ports were installed on both fans for proper cleaning access of fan blades.
15. Were the hood grease cups cleaned?	Yes	
16. Does the system appear to be liquid tight?	Yes	
17. Have exhaust fan belts been inspected/are they working?	Yes	We replaced the fan belts.
18. Have horizontal ducts been cleaned or inspected?	Yes	
19. Have vertical ducts been cleaned or inspected?	Yes	
20. Are sufficient access panels provided?	Yes	a 12x8 access panel was installed for proper cleaning access on the ductwork
21. Is there proper signage on access panels?	Yes	
22. Are all areas of the systems accessible?	No	Fan on main system needs electrical whip extended by 1.5ft unable to properly open the fan and clean underneath the fan blades. Per NFPA 96 Fire code 7.8.2.1.8(a)
23. Are hoods and exhaust systems free of obstructions?	Yes	
24. Cleaning complies with NFPA '96?	Yes	
25. Type of Cooking systems solid fuel, charbroil or Wok?	Other	Flat Top Grill, Fryers, Stove Top, Pizza Oven
26. Are the frequencies adequate?	Yes	
27. Are the precipitators/pollution control clean?	N/A	
28. What condition is the rooftop surface in?	Good	
29. Are there deficiencies in these systems?	No	
30. Are grease containment systems sufficient?	Yes	
31. Are there Type II duct systems?	No	

List deficiencies or comments related:

All systems were cleaned/inspected and a C.O.P was placed on the appropriate hoods.

A record of this service is to be maintained on premise and made available for inspection. It is the owner/tenant's responsibility to maintain the equipment in good working order. It is the responsibility of the cleaning/inspection company technician to report all deficiencies to the proper authority having jurisdiction. If deficiencies are found in these systems, please send a completed copy of this form to the local Fire Department within 48 hours.