COPYRIGHT: Reuse or reproduction of the contents of this document is not permitted without written permission of Bild Architecture LLC



CONCRETE SIZE & REINFORCEMENT SCHEDULE

MARK	TYPE	SIZE	REINFORCING
TYPICAL	TYPICAL FND WALL UNO	8" WIDE x CONT.	- (2) #5 CONT. TOP AND BOT -TYP
			- #4 HORIZ @ 18" | #4 VERT @ 16"
			- SEE SECTION A/S2.1
	TYPICAL CONT FOOTING UNO	24" WIDE x 10" THICK x CONT.	(3) #4 CONT.
* PW1 *	PLANTER WALL FOUNDATION ARCHITECTURALLY EXPOSED	8" WIDE x CONT.	- (2) #5 CONT. TOP AND BOT -TYP
			- #4 HORIZ @ 24" | #4 VERT @ 32"
			- HOOK DOWELS @ 64" O.C.
	PLANTER CONT FOOTING	16" WIDE x 8" THICK x CONT.	(2) #4 CONT.
* CF24 *	CONT STRIP FOOTING	24" WIDE x 10" THICK x CONT.	(3) #4 CONT.
F3.5	ISOLATED FOOTING	36" SQ. x 10" THICK	#4 @ 12" O.C. E.W. @ MID DEPTH

1. ADDITIONAL REINFORCING IS ALSO INDICATED IN PLANS AND SECTION

FOUNDATION/GROUND FLOOR PLAN

0' 1' 5' 10'

SCALE 1/4"=1'-0"

NOTES:

1. ALL CONCRETE REINFORCING STEEL PER PLANS, SCHEDULE AND SECTIONS.
3. SEE S-1.0 FOR STRUCTURAL GENERAL NOTES
4. STEP IN TOP OF FOUNDATION WALL IS INDICATED THUS: , AND SHOWS LOWER SIDE OF WALL.
5. FOOTING TO BEAR 4'-0" MIN BELOW GRADE.
6. T.O. FOOTINGS ARE INDICATED THUS: (XX'-XX").
7. REFERENCE ELEV. 100'-0" = T.O. FIRST FLOOR SHEATHING. COORDINATE ACTUAL USGS ELEVATIONS W/ SITE & CIVIL.
8. STEP IN TOP OF FOOTING IS INDICATED THUS: , AND SHOWS LOWER FOOTING.
9. T.S. = TOP OF SLAB **OR** TOP OF STEEL
10. T.W. = TOP OF WALL

Structural Integrity Consulting Engineers, Inc.
77 Oak Street
Portland, ME, 04101
p. 207-774-4614
f. 866-793-7835
www.structuralintegr.com

BUILD WITH CONFIDENCE

© 2012 Structural Integrity Consulting Engineers, Inc.

SI# 16-0080

STATE OF MAINE
AARON C. JONES
No. 10968
LICENSED
PROFESSIONAL ENGINEER
8/23/2016

Reviewed for Code Compliance
Inspection Services
Portland, Maine
Date: 04/06/17

PROJECT NO.
16-0080
PROJECT NAME
Merrill Street - 7 unit
Portland, ME

REVISIONS
1 - 11/11/16
2 - 12/15/16
3 - 12/20/16
4 - 03/09/17
5 - 04/05/17

PERMIT SET

DRAWN BY **MKL**
SHEET TITLE **FOUNDATION PLAN**

ISSUE DATE **8/23/16**
SHEET SCALE **AS NOTED**

S

S1.1