COPYRIGHT: Reuse or reproduction of the contents of this document is not permitted without written permission of Bild Architecture LLC

CITY OF PORTLAND, MAINE
RESURGAM

Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 10/27/17

CONCRETE SIZE & REINFORCEMENT SCHEDULE

MARK	TYPE	SIZE	REINFORCING
TYPICAL	TYPICAL FND WALL UNO	8" WIDE x CONT.	- (2) #5 CONT. TOP AND BOT -TYP
			- #4 HORIZ @ 18" | #4 VERT @ 16"
			- SEE SECTION A/S2.1
	TYPICAL CONT FOOTING UNO	24" WIDE x 10" THICK x CONT.	(3) #4 CONT.
* PW1 *	PLANTER WALL FOUNDATION ARCHITECTURALLY EXPOSED	8" WIDE x CONT.	- (2) #5 CONT. TOP AND BOT -TYP
			- #4 HORIZ @ 24" | #4 VERT @ 32"
			- HOOK DOWELS @ 64" O.C.
	PLANTER CONT FOOTING	16" WIDE x 8" THICK x CONT.	(2) #4 CONT.
* CF24 *	CONT STRIP FOOTING	24" WIDE x 10" THICK x CONT.	(3) #4 CONT.
* CF36 *	CONT STRIP FOOTING	36" WIDE x 10" THICK x CONT.	#4 @ 12" O.C. E.W. @ MID DEPTH

1. ADDITIONAL REINFORCING IS ALSO INDICATED IN PLANS AND SECTION

FOUNDATION/GROUND FLOOR PLAN

0' 1' 5' 10'

SCALE 1/4"=1'-0"

NOTES:

1. ALL CONCRETE REINFORCING STEEL PER PLANS, SCHEDULE AND SECTIONS.
3. SEE S-1.0 FOR STRUCTURAL GENERAL NOTES
4. STEP IN TOP OF FOUNDATION WALL IS INDICATED THUS: , AND SHOWS LOWER SIDE OF WALL.
5. BOTTOM OF FOOTING TO BEAR 4'-0" MIN BELOW GRADE.
6. TOP OF FOOTINGS ARE INDICATED THUS: (XX'-XX").
7. STEP IN TOP OF FOOTING IS INDICATED THUS: , AND SHOWS LOWER FOOTING.
8. COORDINATE ELEVATION W/ SITE & CIVIL - TYP.

Structural Integrity Consulting Engineers, Inc.
77 Oak Street
Portland, ME, 04101
p. 207-774-4614
f. 866-793-7835
www.structuralinteg.com
BUILD WITH CONFIDENCE
© 2012 Structural Integrity Consulting Engineers, Inc.

SI# 17-0043

REVISIONS
1 3/15/2017 CD
2
3
4
5

PROJECT NO.
16035
PROJECT NAME
7 CUMBERLAND
PORTLAND, ME

DRAWN BY
MKL
SHEET TITLE
FOUNDATION PLAN

ISSUE DATE
8/8/17
SHEET SCALE
AS NOTED

S

S1.1