

COPYRIGHT: Reuse or reproduction of the contents of this document is not permitted without written permission of Bid Architecture LLC

ROOF ASSEMBLY TYPES

GRAPHIC DESCRIPTION		DESCRIPTION											
		<ul style="list-style-type: none"> ADHERED MEMBRANE ROOFING SYSTEM 6" TAPERED EXTRUDED POLYISOCYANURATE (MIN R-30) 5/8" ZIP SYSTEM SHEATHING (AIR BARRIER) 2X12 JOIST PER STRUCTURAL 6 1/2" FIBERGLASS BATT INSULATION (R-20) 7/8" METAL HAT CHANNEL FURRING 5/8" TYPE X GYPSUM BOARD 											
		<table border="1"> <thead> <tr> <th>TYPE</th> <th>FIRE RATING</th> <th>UL NUMBER</th> <th>STC RATING</th> <th>R-VALUE</th> </tr> </thead> <tbody> <tr> <td>R1</td> <td>1-HR</td> <td>SIM L528 & L513</td> <td>N/A</td> <td>53.06</td> </tr> </tbody> </table>				TYPE	FIRE RATING	UL NUMBER	STC RATING	R-VALUE	R1	1-HR	SIM L528 & L513
TYPE	FIRE RATING	UL NUMBER	STC RATING	R-VALUE									
R1	1-HR	SIM L528 & L513	N/A	53.06									

SLAB ASSEMBLY TYPES


GRAPHIC DESCRIPTION		DESCRIPTION											
		<ul style="list-style-type: none"> 4" TROWELED, AND WAXED CONCRETE SLAB. REINFORCE PER STRUCTURAL DRAWINGS. 6 MIL POLY VAPOR BARRIER 2" RIGID INSULATION 6" CRUSHED STONE 											
		<table border="1"> <thead> <tr> <th>TYPE</th> <th>FIRE RATING</th> <th>UL NUMBER</th> <th>STC RATING</th> <th>R-VALUE</th> </tr> </thead> <tbody> <tr> <td>S1</td> <td>N/A</td> <td>N/A</td> <td>N/A</td> <td>10.00</td> </tr> </tbody> </table>				TYPE	FIRE RATING	UL NUMBER	STC RATING	R-VALUE	S1	N/A	N/A
TYPE	FIRE RATING	UL NUMBER	STC RATING	R-VALUE									
S1	N/A	N/A	N/A	10.00									

FLOOR/CEILING ASSEMBLY TYPES

GRAPHIC DESCRIPTION		DESCRIPTION														
		<ul style="list-style-type: none"> 8MM ENGINEERED VINYL PLANK .11" INSULAYMENT PAD 3/4" PLYWOOD T&G SUB-FLOOR 2X12 JOIST PER STRUCTURAL W/ ACOUSTIC BATT INSULATION SOUND ISOLATION CHANNEL HANGERS 7/8" METAL HAT CHANNEL FURRING 2 LAYERS OF 5/8" TYPE X GYPSUM BOARD 														
		<table border="1"> <thead> <tr> <th>TYPE</th> <th>FIRE RATING</th> <th>UL NUMBER</th> <th>IIC RATING</th> <th>STC RATING</th> <th>R-VALUE</th> </tr> </thead> <tbody> <tr> <td>F1</td> <td>1-HR</td> <td>L569</td> <td>48</td> <td>58</td> <td>N/A</td> </tr> </tbody> </table>					TYPE	FIRE RATING	UL NUMBER	IIC RATING	STC RATING	R-VALUE	F1	1-HR	L569	48
TYPE	FIRE RATING	UL NUMBER	IIC RATING	STC RATING	R-VALUE											
F1	1-HR	L569	48	58	N/A											

GRAPHIC DESCRIPTION		DESCRIPTION														
		<ul style="list-style-type: none"> 8MM ENGINEERED VINYL PLANK .11" INSULAYMENT PAD 3/4" PLYWOOD T&G SUB-FLOOR 2X12 JOIST PER STRUCTURAL W/ ACOUSTIC BATT INSULATION SOUND ISOLATION CHANNEL HANGERS 5/8" TYPE X GYPSUM BOARD 7/8" METAL HAT CHANNEL FURRING 5/8" TYPE X GYPSUM BOARD 														
		<table border="1"> <thead> <tr> <th>TYPE</th> <th>FIRE RATING</th> <th>UL NUMBER</th> <th>IIC RATING</th> <th>STC RATING</th> <th>R-VALUE</th> </tr> </thead> <tbody> <tr> <td>F2</td> <td>2-HR</td> <td>SIM L511</td> <td>48</td> <td>58</td> <td>N/A</td> </tr> </tbody> </table>					TYPE	FIRE RATING	UL NUMBER	IIC RATING	STC RATING	R-VALUE	F2	2-HR	SIM L511	48
TYPE	FIRE RATING	UL NUMBER	IIC RATING	STC RATING	R-VALUE											
F2	2-HR	SIM L511	48	58	N/A											

Bid Architecture
 PO Box 8235
 Portland, ME
 04104
 207.408.0168
 evan@bidarchitecture.com



PROJECT NO. **16035**
 PROJECT NAME **7 CUMBERLAND PORTLAND, ME**

REVISIONS	DATE	DESCRIPTION
1	03-15-2017	
2		
3		
4		
5		

PERMIT SET
NOT FOR CONSTRUCTION
CONSTRUCTION ASSEMBLIES

DRAWN BY **EAC**
 SHEET TITLE **CONSTRUCTION ASSEMBLIES**

ISSUE DATE **2/24/17**
 SHEET SCALE **NTS**



101 CITY OF PORTLAND
 PLANNING DEPARTMENT
 SUBJECT TO CONDITIONS OF APPROVAL
 AND STANDARDS