



Slimline double hung vinyl windows feature a sleek, fully-welded sash profile and a fully-welded frame. This unique design minimizes the width of the sash frames to increase your exterior view. We've applied the latest technology to produce an attractive window at an affordable price, without compromising on features. Slimline offers high-quality design, value and custom manufacturing for a perfect fit. Lighten up your view of life with Slimline.

- ENERGY STAR® qualified with optional ENERGY STAR glazing package upgrade
- Low profile sweep locks
- Factory calibrated block & tackle sash balances never need adjustment or lubrication
- Ventilation limit latches that keep top or bottom sash partially open
- Fiberglass half screen (standard)
- C50 upgrade available



Tilt-in top and bottom sash for easy cleaning.





Vinyl Color




Grids

Contoured GBG (Grids Between Glass)



Color-Matched

Configurations



Custom configurations also available.

Glazing Packages

- Clear Insulated
- ENERGY STAR
- Low-E
- Low-E/Argon
- Double Low-E/Argon
- Obscured
- Tempered

Additional Options

- DP 50 Upgrade
- Structural Mullion
- Half or Full Screen
- Fiberglass Wire
- Aluminum Wire
- Virtually Invisible (VIEWS)

Hardware



Low-Profile Sweep Lock (White is standard)



White





Thermal Performance

For the most up to date structural and thermal performance values, as well as other product specifications, visit harveybp.com.

Glazing	U-Factor	SHGC	Visible Light Transmittance	ENERGY STAR Compliance	
Clear Insulated	0.46	0.60	0.62		
ENERGY STAR	0.27	0.31	0.55	N, NC	

ENERGY STAR: This package includes everything that is needed for a product to meet ENERGY STAR requirements. Glazing, gas, glass thickness, etc. will vary by window and usually includes Low-E coating and Argon gas. This glazing package does qualify for ENERGY STAR.

U-factor measures the rate of non-solar heat transfer from one side of the window to the other. Heat transfer implies both heat loss out of a living space during cold weather and non-solar heat gain during hot summer months. The lower the U-factor, the better the performance.

Solar Heat Gain Coefficient (SHGC) measures how well a product blocks heat from the sun. The lower the SHGC, the better a product is at blocking unwanted heat gain.

Visible Transmittance (VT) measures how much light comes through a product. The higher the VT, the more light that comes through.



About Harvey Building Products

Harvey has built a solid reputation as a leading manufacturer and distributor of quality building products. A privately owned and operated business with over 50 years' experience, Harvey Building Products is known for outstanding craftsmanship and superior service as well as standing behind every product we make. In addition to manufacturing durable, attractive windows, doors and patio rooms, Harvey distributes a full line of highly respected building products to professional contractors and builders throughout the Northeast.

We understand what it takes to be part of your home.™



Harvey Building Products 1400 Main Street Waltham, MA 02451-1623 USA 800-9HARVEY (800-942-7839)



Information about Harvey Building Products and our products and services can be found at harveybp.com.







