



PROJECTION ROOF FRAMING PLAN

NOTES:

- 1) - INDICATES SPAN DIRECTION OF 5/8" SHEATHING
- 2) PROVIDE SIMPSON H2.5 HURRICANE TIES AND PLYWOOD OR LSL WEB BLOCKING ON EACH SIDE OF TJI JOIST WEB AT ALL ROOF BEAM BEARING LOCATIONS PER MANUF. REQS (TYP)
- 3) BEARING WALLS: 2X6 STUDS ALIGNED WITH BEAMS
- 4) LVL CARRYING BEAMS ARE TO BEAR DIRECTLY ON COLUMNS.
- 5) TJI WEB BLOCKING
- 6) PROVIDE 1 1/8" RIM BOARD AT EXTERIOR WALLS (TYP)
- 7) H.D. - INDICATES SIMPSON HOLDOWN ANCHOR LOCATIONS. REFER TO SCHEDULE ON S2.2. COORD H.D. LOCATION W/ POSTS. REFER TO SHEARWALLELEVATIONS FOR POST REQUIREMENTS.
- 8) HX - REFER TO HEADER SCHEDULE ON SHEET S0.0.
- 9) REFER TO HANGER SCHEDULE ON SHEET S0.0.
- 10) - INDICATES SHEARWALL BELOW. REFER TO SHEARWALL ELEVATIONS.



HOWARD ST.
RESIDENCE

PORTLAND, ME

PROJECTION FRAMING PLAN

DATE: 07/11/2017

SHEET: S1.5