COPYRIGHT: Reuse or reproduction of the contents of this document is not permitted without written permission of Bild Architecture LLC

FINISH SCHEDULE										
UNIT #	ROOM	FLOOR	WALLS				BASE	CEILING	RAILINGS & CASEWORK	NOTES
			N	S	E	W				
–	HALL 1	WD	–	–	–	–	–	–	–	1
–	HALL 2	WD	PNT	PNT	PNT	PNT	W			1
1 & 2	LIVING	WD	PNT	PNT	PNT	PNT	W	GYP		
1 & 2	DINING	WD	PNT	PNT	PNT	PNT	W	GYP		
1 & 2	KITCHEN	WD	PNT	PNT	PNT	PNT	W	GYP		2
1 & 2	BATH	CT	PNT	PNT	PNT	PNT		GYP		
1 & 2	½ BATH	CT	PNT	PNT	PNT	PNT		GYP		
1 & 2	BEDROOM 1	CPT	PNT	PNT	PNT	PNT	W	GYP		
1 & 2	BEDROOM 2	CPT	PNT	PNT	PNT	PNT	W	GYP		
1 & 2	CLOSET	WD	PNT	PNT	PNT	PNT	W	GYP		
–	HALL 3	WD	PNT	PNT	PNT	PNT	W			1
–	HALL 4	WD	PNT	PNT	PNT	PNT	W			1
3 & 4	LIVING	WD	PNT	PNT	PNT	PNT	W	GYP		
3 & 4	DINING	WD	PNT	PNT	PNT	PNT	W	GYP		
3 & 4	KITCHEN	WD	PNT	PNT	PNT	PNT	W	GYP		2
3 & 4	BATH	CT	PNT	PNT	PNT	PNT		GYP		
3 & 4	½ BATH	CT	PNT	PNT	PNT	PNT		GYP		
3 & 4	BEDROOM 1	CPT	PNT	PNT	PNT	PNT	W	GYP		
3 & 4	BEDROOM 2	CPT	PNT	PNT	PNT	PNT	W	GYP		
3 & 4	CLOSET	WD	PNT	PNT	PNT	PNT	W	GYP		
–	HALL 5	WD	PNT	PNT	PNT	PNT	W			1
–	HALL 6	WD	PNT	PNT	PNT	PNT	W			1
5 & 6	LIVING	WD	PNT	PNT	PNT	PNT	W	GYP		
5 & 6	DINING	WD	PNT	PNT	PNT	PNT	W	GYP		
5 & 6	KITCHEN	WD	PNT	PNT	PNT	PNT	W	GYP		2
5 & 6	BATH	CT	PNT	PNT	PNT	PNT		GYP		
5 & 6	½ BATH	CT	PNT	PNT	PNT	PNT		GYP		
5 & 6	BEDROOM 1	CPT	PNT	PNT	PNT	PNT	W	GYP		
5 & 6	BEDROOM 2	CPT	PNT	PNT	PNT	PNT	W	GYP		

FINISH SCHEDULE NOTES:

1. REFINISH WOOD STAIRS IN HALLWAYS
2. STONE COUNTERTOPS W/ 4" STONE BACK
3. 5-1/4" WOOD TRIM

LEGEND:

PNT	PAINT
CPT	CARPET
WD	ENGINEERED WOOD
W	WOOD BASE
CT	CUSTOM TILE
EXIST	EXISTING TO REMAIN
GYP	GYPSUM WALL BOARD

PAINT SCHEDULE:

PNT BENJAMIN MOORE COLOR TBD
AURA ZERO VOC PAINT,
WALLS = EGGSHELL, SATIN FINISH
CEILINGS = FLAT

4 — 2X4 WOOD FRAMING WALL

4 3/4" ACTUAL WALL THICKNESS

A4 — 2X4 WOOD FRAMING ACOUSTICAL WALL

4 3/4" ACTUAL WALL THICKNESS

L4 — 2X4 WOOD FRAMING ACOUSTICAL AND LOAD BEARING WALL

4 3/4" ACTUAL WALL THICKNESS

EL — EXISTING WOOD FRAMING ACOUSTICAL AND LOAD BEARING WALL

MATCH WALL THICKNESS TO EXISTING

F6 — 2X6 WOOD FRAMING FIRE WALL
1 HOUR RATED UL-U311 ASSEMBLY
STC RATING: 50-54

MATCH WALL THICKNESS TO EXISTING

NOTE:

PENETRATIONS, JOINTS, OPENINGS, AND DUCTS INTERRUPTING ANY FIRE RATED ASSEMBLY SHALL CONFORM WITH IBC CHAPTER 7.

E6 — EXISTING WOOD FRAMING FIRE WALL
1 HOUR RATED UL-313 ASSEMBLY
STC RATING: 50-54

MATCH WALL THICKNESS TO EXISTING

NOTE:

PENETRATIONS, JOINTS, OPENINGS, AND DUCTS INTERRUPTING ANY FIRE RATED ASSEMBLY SHALL CONFORM WITH IBC CHAPTER 7.

Bild Architecture
PO Box 8235
Portland, ME
04104
207.408.0168
evan@bildarchitecture.com

LICENSED ARCHITECT
EVAN A. CARROLL
No. 3687
STATE OF MAINE

Reviewed for Code Compliance
Inspections Division
Date: 06/29/16

PERMIT SET

REVISIONS
1 -
2 -
3 -
4 -
5 -

PROJECT NO.
15027
PROJECT NAME
15-17 MERRILL STREET
PORTLAND, ME

DRAWN BY
EMW
SHEET TITLE
FINISHES AND PARTITIONS

ISSUE DATE
4/15/16
SHEET SCALE
1/4" = 1'-0"

A

6