COPYRIGHT: Reuse or reproduction of the contents of this document is not permitted without written permission of Bild Architecture LLC

DOOR SCHEDULE									
DOOR #	FROM	TO	SIZE	DOOR MATERIAL	DOOR TYPE	DOOR RATING	FRAME	HARDWARE SET	NOTES
099, 099	EXTERIOR	HALL	3'-0" X 7'-0"	3'-0" X 7'-0"	4	1 HR	EXISTING	06	1
100, 200	HALLWAY	LIVING	3'-0" X 7'-0"	SOLID CORE	1	1 HR	WOOD	01	–
101, 201	KITCHEN	BED #2	2'-6" X 7'-0"	SOLID CORE	1	–	WOOD	03	–
102, 202	BED 2	CLOSET	5'-0" x 7'-0"	SOLID CORE	2	–	WOOD	04	–
103, 203	KITCHEN	BED 1	2'-6" x 7'-0"	SOLID CORE	1	–	WOOD	03	–
104, 204	KITCHEN	1\2 BATH	2'-6" x 7'-0"	SOLID CORE	1	–	WOOD	03	–
105, 205	BED 1	BATH	2'-6" X 7'-0"	SOLID CORE	1	–	WOOD	03	–
106, 206	DINING	STAIR CLOSET	2'-6" X 7'-0"	SOLID CORE	1	–	WOOD	02	–
107, 207	DINING	COAT CLOSET	2'-6" x 7'-0"	SOLID CORE	1	–	WOOD	02	–
108, 208	BED 1	EXTERIOR	3'-0" X 6'-8"	SOLID CORE	3	–	WOOD	05	
109, 209	BED 1	CLOSET	5'-0" x 7'-0"	SOLID CORE	2	–	WOOD	04	–
300, 400	HALLWAY	LIVING	3'-0" X 7'-0"	SOLID CORE	1	1 HR	WOOD	01	–
301, 401	KITCHEN	BED #2	2'-6" X 7'-0"	SOLID CORE	1	–	WOOD	03	–
302, 402	BED 2	CLOSET	5'-0" x 7'-0"	SOLID CORE	2	–	WOOD	04	–
303, 403	KITCHEN	BED 1	2'-6" x 7'-0"	SOLID CORE	1	–	WOOD	03	–
304, 404	KITCHEN	½ BATH	2'-6" x 7'-0"	SOLID CORE	1	–	WOOD	03	–
305, 405	BED 1	BATH	2'-6" X 7'-0"	SOLID CORE	1	–	WOOD	03	–
306, 406	BED 1	CLOSET	5'-0" x 7'-0"	SOLID CORE	2	–	WOOD	04	–
307, 407	BED 1	EXTERIOR	3'-0" X 6'-8"	SOLID CORE	3	–	WOOD	05	–
308, 408	KITCHEN	CLOSET	2'-6" X 7'-0"	SOLID CORE	1	–	WOOD	02	–
500, 600	HALLWAY	HALL	3'-0" X 7'-0"	SOLID CORE	1	1 HR	WOOD	01	–
501, 601	HALL	BED #2	2'-6" X 7'-0"	SOLID CORE	1	–	WOOD	03	–
502, 602	BED 2	CLOSET	4'-0" x 7'-0"	SOLID CORE	2	–	WOOD	04	–
503, 603	HALL	BED 1	2'-6" x 7'-0"	SOLID CORE	1	–	WOOD	03	–
504, 604	BED 1	CLOSET	4'-0" x 7'-0"	SOLID CORE	2	–	WOOD	04	–
505, 605	BED 1	BATH	2'-6" x 7'-0"	SOLID CORE	1	–	WOOD	03	–
506, 606	KITCHEN	EXTERIOR	3'-0" X 6'-8"	SOLID CORE	3	–	WOOD	05	–
507, 607	HALL	½ BATH	2'-6" x 7'-0"	SOLID CORE	1	–	WOOD	03	–
508, 608	DINING	CLOSET	3'-8" X 7'-0"	SOLID CORE	2	–	WOOD	04	–
509, 609	DINING	CLOSET	3'-8" X 7'-0"	SOLID CORE	2	–	WOOD	04	–

TYPE 1 TYPE 2 TYPE 3 TYPE 4

GENERAL DOOR SCHEDULE NOTES:

- ALL DOOR HANDLES TO BE ADA COMPLIANT LEVER HANDLES.
- DOORS WITHIN UNITS TO BE CLEAR FINISH FLUSH PANEL BIRCH

DOOR SCHEDULE NOTES:

1. KEEP EXISTING WOOD FRAME

HARDWARE SETS:

01 UNIT ENTRY DOORS: PEEP HOLE, (3) HINGES, SOFT CLOSE DAMPER, STRIKE, DOOR STOP, SINGLE CYLINDER DEADBOLT, LOCKSET, THROW-BOLT, LATCH ASSEMBLY, LEVER, DOOR CHIME ON

02 CLOSET DOORS: (3) HINGES, PASSAGE LOCKSET

03 BEDROOM & BATH DOORS: (3) HINGES, PRIVACY LOCKSET, CORES

04 CLOSET DOORS: (3) HINGES, CORES

05 DECK DOORS: (3) HINGES. SINGLE CYLINDER DEADBOLT, LOCKSET, THRESHOLD,

06 BUILDING ENTRY DOOR: (3) HINGES, SINGLE CYLINDER DEADBOLT, LEVER LOCKETSET, THRESHOLD,

DECK FRAMING PLAN

0 4'-0" SCALE: 1/4" = 1'-0"

WINDOW SCHEDULE							
TYPE	SIZE (ROUGH OPENING)	MATERIAL	OPERATION	HEAD DETAIL	JAMB DETAIL	SILL DETAIL	NOTES
A	5'-8" X 2'-8""	PVC	DOUBLE HUNG	VARIES	VARIES	VARIES	1, 6
B	5'-8" X 2'-5"	PVC	CASEMENT	–	–	–	1, 6
C	5'-8" X 3'-0"	PVC	DOUBLE HUNG	–	–	–	1
D	5'-8" X 1'-8"	PVC	DOUBLE HUNG	VARIES	VARIES	VARIES	1

WINDOW A EGRESS WINDOW B EGRESS WINDOW C WINDOW D

WINDOW SCHEDULE NOTES:

1. FIELD VERIFY ALL DIMENSIONS
2. VERIFY EXISTING ROUGH OPENING IN FIELD.
3. WINDOW TO BE THERMALLY BROKEN.
4. 1X4 TRIM AROUND WINDOWS
5. SILL W/ APRON AT WINDOWS (TYP)
6. EGRESS WINDOWS NEED A NET CLEAR OPENING OF 5.7 SF AND CLEAR OPENING DIMENSIONS OF 24" HIGH BY 20" WIDE

WINDOW SPECIFICATIONS:

1. Size and window configuration.	See Window Schedule
2. Color options.	TBD
3. Factory Mulling Capability.	-
4. Design Pressure Rating	25
5. U Factor	0.35 or lower
6. Material	See Window Schedule
7. Glazing Type	Triple glazing Preferred (best financial value for the lowest U-factor)
8. Hardware type.	TBD
9. Exterior Washing Capability	Washing from interior preferred
10. Warranty (Window & glazing units)	-
11. Insect Screens	Standard Insect Screens

Bild Architecture
PO Box 8235
Portland, ME
04104
207.408.0168
evan@bildarchitecture.com

LICENSED ARCHITECT EVAN A. CARROLL No. 3687 STATE OF MAINE

Reviewed for Code Compliance Inspections Division Approved as Noted Date: 06/29/16

PROJECT NO. 15027
PROJECT NAME 15-17 MERRILL STREET PORTLAND, ME

PERMIT SET

REVISIONS 1 - 2 - 3 - 4 - 5 -

DRAWN BY EMW
SHEET TITLE DOOR/WINDOW

ISSUE DATE 4/15/16
SHEET SCALE 1/4" = 1'-0"

A

5