COPYRIGHT: Reuse or reproduction of the contents of this document is not permitted without written permission of Bild Architecture LLC

3 WEST ELEVATION
0 8'-0" SCALE: 1/8" = 1'-0"

4 SOUTH ELEVATION
0 8'-0" SCALE: 1/8" = 1'-0"

X DEMOLITION KEYNOTES:

1. EXISTING ROOF AND SHINGLES TO STAY.
2. DEMO EXISTING WINDOW
3. DEMO EXISTING SIDING AND TRIM. LEAVE GUTTER & DOWN SPOUTS INTACT OR SAVE TO REINSTALL
4. DEMO EXISTING STAIRS INCLUDING TREADS, RISERS, STRINGERS AND RISERS.
5. DEMO EXISTING DOOR, FRAME AND WALL TO PREPARE FOR WINDOW
6. PRESERVE EXISTING WOOD WORK.
7. IF SALVAGEABLE – PRESERVE AND PROTECT ANY UNCOVERED WOOD WORK FOUND AROUND BAY WINDOWS
8. CUT HOLE INTO FOUNDATION WALL AND EXCAVATE FOR FUTURE BULKHEAD
9. PREPARE WINDOW OPENING FOR NEW DOOR

1 NORTH ELEVATION
0 8'-0" SCALE: 1/8" = 1'-0"

2 EAST ELEVATION
0 8'-0" SCALE: 1/8" = 1'-0"

Bild Architecture
PO Box 8235
Portland, ME
04104
207.408.0168
evan@bildarchitecture.com

LICENSED ARCHITECT
EVAN A. CARROLL
No. 3687
STATE OF MAINE

Reviewed for Code Compliance
Inspections Division
Date: 06/29/16

PROJECT NO.
15027
PROJECT NAME
15-17 MERRILL STREET
PORTLAND, ME

REVISIONS
1 -
2 -
3 -
4 -
5 -

PERMIT SET

DRAWN BY
EMW
SHEET TITLE
DEMO - ELEV

ISSUE DATE
4/15/16
SHEET SCALE
1/4" = 1'-0"

D

2