COPYRIGHT: Reuse or reproduction of the contents of this document is not permitted without written permission of Bild Architecture LLC

WINDOW SCHEDULE				
TYPE	SIZE (ROUGH OPENING)	MATERIAL	OPERATION	NOTES
A	6'-0" X 6'-0"	-	CASEMENT+ AWNING	1,3
B	3'-0" X 6'-0"	-	CASEMENT+ AWNING	1,3
C	3'-0" X 3'-0"	-	AWNING	1,3
D	2'-6" X 3'-0"	-	AWNING	1,3
E	2'-0" X 3'-0"	-	AWNING	1,3
F	1'-6" X 2'-0"	-	FIXED	1,3

WINDOW SCHEDULE NOTES:

1. ALL WINDOWS TO HAVE A MAXIMUM U-FACTOR OF 0.35
2. WINDOWS LABELED "EGRESS WINDOW" IN PLAN MUST COMPLY WITH: MIN AREA: 5.7SF
   MIN HEIGHT: 24"
   MIN WIDTH: 20"
3. WINDOWS TP BE THERMALLY BROKEN
4. SEE DOOR SCHEDULE

WINDOW SPECIFICATIONS:

1. Size and window configuration.	See Window Schedule
2. Color options.	To be selected
3. Factory Mulling Capabilty.	Preferred
4. Design Pressure Rating	25
5. U Factor	0.35 or lower
6. Material	To be selected
7. Glazing Type	To be selected
8. Hardware type.	To be selected
9. Exterior Washing Capability	Washing from interior preferred
10. Warranty (Window & glazing units)	10 years
11. Insect Screens	Standard Insect Screens

DOOR SCHEDULE									
DOOR #	FROM	TO	SIZE	DOOR MATERIAL	DOOR TYPE	DOOR RATING	FRAME	HARDWARE SET	NOTES
001	EXTERIOR	GARAGE	14'-0" X 8'-0"	WD	5	-	WD		4
002,003	EXTERIOR	VESTIBULE	3'-0" X 8'-0"	?	1	-	WD	01	1
004, 005	GARAGE	VESTIBULE	3'-0" X 6'-8"	?	3	1HR	HM	02	
006, 007	GARAGE	STORAGE	3'-0" X 6'-8"	SOLID CORE	3	-	HM	05	
101,201	LIVING	POWDER ROOM	2'-4" X 6'-8"	SOLID CORE	4	-	WD	07	
301, 401	HALLWAY	BEDROOM 1	2'-6" X 6'-8"	SOLID CORE	3	-	WD	03	
302, 402	HALLWAY	BEDROOM 2	2'-6" X 6'-8"	SOLID CORE	3	-	WD	03	
303, 403	HALLWAY	BATH	2'-6" X 6'-8"	SOLID CORE	1	-	WD	03	
304,404	HALLWAY	W/D	5'-0" X 6'-8"	SOLID CORE	6	-	WD	06	
305,405	BEDROOM	CLOSET	6'-0" X 6'-8"	SOLID CORE	6	-	WD	06	
306,406	BEDROOM	CLOSET	6'-0" X 6'-8"	SOLID CORE	6	-	WD	06	
307,407	BEDROOM	BATH	2'-6" X 6'-8"	SOLID CORE	4	-	WD	07	3
501, 601	HALLWAY	MASTER BEDROOM	2'-6" X 6'-8"	SOLID CORE	3	-	WD	03	
502, 602	M. BEDROOM	M.BATH	2'-6" X 6'-8"	SOLID CORE	3	-	WD	03	
503, 603	M. BEDROOM	CLOSET	2'-6" x 6'-8"	SOLID CORE	4	-	WD	07	
504, 604	HALLWAY	DECK	3-0" X 7'-0"	COMPOSITE	2	-	COMP	04	1

DOOR TYPES

GENERAL DOOR SCHEDULE NOTES:

- ALL DOOR HANDLES TO BE ADA COMPLIANT LEVER HANDLES.
- ALL INTERIOR DOOR HARDWARE FINISH TBD
- DOORS WITHIN UNITS FINISH TBD
- PROVIDE A COMMON SPACES KEY FOR TENANT ENTRANCES AND STORAGE AREA (ISSUED TO EACH TENANT)

DOOR SCHEDULE NOTES:

1. SAFETY GLAZING
2. INSULATED
3. OPTIONAL
4. MANUFACTURER TBD
5. -

HARDWARE SETS:

01	ENTRY DOORS:	(3) HINGES, STRIKE, DOOR STOP, THRESHOLD, SWEEP ENTRY LOCKSET, GASKET, LEVER, METAL PROTECTIVE TRIM, CLOSER, SINGLE CYLINDER DEADBOLT
02	GARAGE DOORS	(3) HINGES, STRIKE, DOOR STOP, LEVER, ENTRY LOCKSET, CLOSER, SINGLE CYLINDER DEADBOLT
03	BATH/BED DOORS:	(3) HINGES, STRIKE, DOOR STOP, LEVER, BED/BATH LOCKSET
04	PATIO DOORS:	(3) HINGES, ESCUTCHEON PLATE, LEVER, DEADBOLT LOCKSET, THRESHOLD
05	STORAGE DOORS	(3) HINGES, STRIKE, DOOR STOP, LEVER, STORAGE LOCKSET
06	FOLDING DOORS	TRACK LENGTH, TOP PIVOTS, TOP PIVOT LOCKS, DOOR GUIDES, BOTTOM PIVOTS, BOTTOM PIVOT BRACKETS, TRACK STOPS, PANEL HINGES, PANEL ALIGNER, DOOR KNOBS
07	POCKET DOOR	TRACK, COASTERS, DOOR GUIDE, DECORATIVE PULL

Reviewed for Code Compliance
Inspections Division
Portland, Maine
Date: 08/30/17

Bild Architecture
PO Box 8235
Portland, ME
04104
207.408.0168
evan@bildarchitecture.com

LICENSED ARCHITECT
5/8/16
EVAN A. CARROLL
No. 3687
STATE OF MAINE

PROJECT NO.
17002
PROJECT NAME
5 MERRILL STREET
PORTLAND, ME 04101

REVISIONS
1 -
2 -
3 -
4 -
5 -

PERMIT SET
NOT FOR CONSTRUCTION

DRAWN BY
AEW/KBS
SHEET TITLE
SCHEDULES

ISSUE DATE
5/8/17
SHEET SCALE
3/8" = 1'-0"

A

601