GENERAL NOTES

1. NOT ALL SYMBOLS INDICATED IN THE LEGEND APPEAR ON THE DRAWINGS. COORDINATE WORK ACCORDINGLY. COMPLY WITH SPECIFICATIONS AND NOTES BELOW AS APPLICABLE.
2. ALL RECEPTACLES SHALL BE INSTALLED 18" AFF TO CENTERLINE OF BOX UNLESS NOTED OTHERWISE.
3. MOUNT PANELS IN RESIDENTIAL SPACES SO NO CIRCUIT BREAKER HANDLE IS HIGHER THAN 44" AFF.
4. ALL WIRING SHALL BE COPPER UNLESS DESIGNATED AS "AL". UNLESS OTHERWISE NOTED ALL WIRING SHALL BE 2*12 AWG AND 1*12 EQUIPMENT GROUNDING CONDUCTOR. HOMERUNS FED FROM A 20A-1P, 120V CIRCUIT IN EXCESS OF 70' SHALL BE *10 AWG.
5. CONNECT BATTERY BACKED EMERGENCY AND EXIT LIGHTING TO NEAREST LIGHTING CIRCUIT AHEAD OF ANY SWITCHING. CONNECT REMOTE HEADS WITH *10 AWG COPPER CONDUCTORS. AC EXIT FIXTURES SHALL BE CONNECTED TO NEAREST EMERGENCY CIRCUIT OR AS INDICATED.
6. TEST ALL EMERGENCY LIGHTING UNITS FOR PROPER OPERATION OF LAMPS AND BATTERIES.
7. ALL WORK SHALL COMPLY WITH NFPA70, NFPA72, NFPA101 & ALL FEDERAL, STATE & LOCAL REGULATIONS.
8. ALL PENETRATIONS THROUGH FLOORS, RATED WALLS AND PARTITIONS SHALL BE SEALED WITH UL APPROVED FIRE SEALANT MATERIAL TO MAINTAIN FIRE RATING FOR THE SEPARATION.
9. ALL ENCLOSURES, CONDUIT BODIES AND THEIR COVERS CONTAINING FIRE ALARM SYSTEM CONDUCTORS SHALL BE PAINTED RED.
10. AN EQUIPMENT GROUNDING CONDUCTOR SHALL BE INSTALLED WITH ALL FEEDERS AND BRANCH CIRCUITS. SIZE IN ACCORDANCE WITH NFPA 70 ARTICLE 250.
11. COORDINATE INSTALLATION AND LOCATION OF VOICE AND CABLE TV OUTLETS WITH OWNER.
12. THE CONTRACTOR SHALL SET ALL ELECTRONIC BREAKERS TO SPECIFIED TRIP SETTINGS BEFORE ENERGIZING EQUIPMENT.
13. PROVIDE EXPANSION FITTINGS FOR ALL UNDERGROUND RACEWAYS ENTERING ENCLOSURES ATTACHED TO FIXED STRUCTURES.
14. OUTDOOR RECEPTACLE COVERS SHALL COMPLY WITH NFPA 70 - ARTICLE 406.9.
15. ALL CONDUCTOR INSULATION FOR BUILDING WIRE SHALL BE THWN/THHN UNLESS NOTED OTHERWISE.
16. PROVIDE LABEL ON SERVICE EQUIPMENT INDICATING AVAILABLE SHORT CIRCUIT CURRENT OBTAIN VALUES FROM ENGINEER.
17. PROVIDE ARC-FALUT CIRCUIT BREAKERS FOR ALL CIRCUITS WITHIN TENANT PANELS. PROVIDE ARC FAULT LABELS PER NFPA 70-ARTICLE 110.2.
18. PROVIDE GFCI RATED CIRCUIT BREAKERS FOR DISHWASHER, REFRIGERATOR, WASHING MACHINE AND DRYER CIRCUIT.
19. IF BUILDING REQUIRES TWO SERVICE ENTRANCES, PROVIDE SIGNS PER NFPA 70-230.
20. OUTLETS INSTALLED IN FIRE RATED WALLS BACK TO BACK SHALL BE SEPARATED BY 24" MINIMUM OR BE PROTECTED WITH "PUTTY PADS" PER 2009 INTERNATIONAL BUILDING CODE SECTION 713.3.2
21. PROVIDE AIR VAPRO BARRIER BOXES FOR WIRING DEVICES IN EXTERIOR WALLS AND INTERIOR SOUND CONTROL WALLS BETWEEN RESIDENT ROOMS. INSTALL PER MANUFACTURER'S INSTRUCTIONS. PROVIDE LESSCO MODEL NUMBER: VAPORBOX
22. MINIMUM WIRE SIZE ON ALL BRANCH CIRCUITS SHALL BE *12.

ABBREVIATIONS

A	AMP
AC	ALTERNATING CURRENT, ABOVE COUNTER
ADA	AMERICANS WITH DISABILITIES ACT
AF	AMP FRAME
AFCI	ARC FAULT CIRCUIT INTERRUPTER
AFF	ABOVE FINISHED FLOOR
AFG	ABOVE FINISHED GRADE
AIC	AMPERES INTERRUPTING CAPACITY
AL	ALUMINUM
AT	AMP TRIP
ATC	AUTOMATIC TEMPERATURE CONTROL
ATS	AUTOMATIC TRANSFER SWITCH
AWG	AMERICAN WIRE GAUGE
BLDG	BUILDING
C	CONDUIT
CB	CIRCUIT BREAKER
CI	CAST IRON
CKT	CIRCUIT
℄	CENTERLINE
CMP	CENTRAL MAINE POWER (ELECTRIC UTILITY)
CMU	CONCRETE MASONRY UNIT
CT	CURRENT TRANSFORMER
CONC	CONCRETE
CS	CARBON STEEL
CU	COPPER
CUH	CABINET UNIT HEATER
DL	DAMP LOCATION
EC	ELECTRICAL CONTRACTOR
EF	EXHAUST FAN
ER	EXISTING REMAINS IN PLACE
ERL	EXISTING RELOCATE
ERM	EXISTING REMOVE
EUH	ELECTRIC UNIT HEATER
EWC	ELECTRICAL WATER COOLER
FACP	FIRE ALARM CONTROL PANEL
FAPS	FIRE ALARM PULL STATION
FRP	FIBER REINFORCED PLASTIC
FVNR	FULL VOLTAGE, NON-REVERSING
FWU	FURNISHED WITH UNIT
DC	DIRECT CURRENT
GFI	GROUND FAULT INTERRUPTER
GND	GROUND
HID	HIGH INTENSITY DISCHARGE
HOA	HAND-OFF-AUTOMATIC
HP	HORSEPOWER
HPS	HIGH PRESSURE SODIUM
HZ	HERTZ
ICB	INSULATED CASE CIRCUIT BREAKER
JB	JUNCTION BOX
KAIC	THOUSAND AMP INTERRUPTING CAPACITY
KCMIL	THOUSAND CIRCULAR MIL
KV	THOUSAND VOLTS
KVA	THOUSAND VOLT-AMPS
KW	THOUSAND WATTS (KILOWATT)
LED	LIGHT EMITTING DIODE
LP	LIGHTING PANELBOARD
LTG	LIGHTING
LSIG	LONG TIME, SHORT TIME, INSTANTANEOUS, GROUND FAULT CIRCUIT BREAKER TRIP FUNCTIONS AS INDICATED
MCC	MOTOR CONTROL CENTER
MCCB	MOLDED CASE CIRCUIT BREAKER
MCB	MAIN CIRCUIT BREAKER
MDP	MAIN DISTRUBITION PANEL
MH	MANHOLE
MLO	MAIN LUGS ONLY
MTS	MANUAL TRANSFER SWITCH
NC	NORMALLY CLOSED OF NURSE CALL
NEC	NATIONAL ELECTRICAL CODE
NFPA	NATIONAL FIRE PROTECTION ASSOCIATION
NL	NIGHT LIGHT
NO	NORMALLY OPEN
NO.	NUMBER
OL	OVERLOAD
P	POLE
PA	PUBLIC ADDRESS
PB	PUSH BUTTON
PF	POWER FACTOR
PH	PHASE
PNL	PANEL
TP1-2	TELE-POWER POLE - POLE AND CIRCUIT NUMBER AS INDICATED
PSNH	PUBLIC SERVICE OF NEW HAMPSHIRE (ELECTRIC UTILITY)
PT	POTENTIAL TRANSFORMER
PVC	POLYVINYL CHLORIDE
RL	ELECTRICAL EQUIPMENT TO BE RELOCATED
RM	ELECTRICAL EQUIPMENT TO REMAIN
RSC	RIGID STEEL CONDUIT
RTU	ROOF TOP UNIT
RV	ELECTRICAL EQUIPMENT TO REMOVE
RVNR	REDUCED VOLTAGE, NON-REVESING
SB	SMART BOARD
SF	SUPPLY FAN
SLD	SINGLE LINE DIAGRAM
SM	MANUAL MOTOR STARTER SWITCH WITH THERMAL OVERLOAD DEVICE, MOUNTED AT UNIT
SS	SOLID STATE
SWBD-1	SWITCHBOARD NUMBER AS DESIGNATED
TC	TIME CLOCK
TS	TRANSFER SWITCH
TYP	TYPICAL
UG	UNDERGROUND
V	VOLT
VA	VOLT-AMPERE
VFD	VARIABLE FREQUENCY DRIVE
W	WATT
W/	WITH
WP	WEATHERPROOF
XFMR	TRANSFORMER
3PH	THREE PHASE
4W	FOUR WIRE
3W	THREE WIRE

SYMBOL LEGEND

- SURFACE MOUNTED POWER PANEL, SEE PANEL SCHEDULES FOR RATING
- RECESSED MOUNTED POWER PANEL, SEE PANEL SCHEDULES FOR RATING
- H, DS, DW — JUNCTION BOX, "H" DENOTES RANGE HOOD, "DS" DENOTES DISPOSAL, "DW" DENOTES DISHWASHER
- DUPLEX RECEPTACLE, 20A, 125V SPEC GRADE GROUNDING TYPE, TAMPER PROOF AND MATCHING PLATE. MOUNT 18" AFF UNLESS NOTED OTHERWISE.
- GFI — GROUND FAULT DUPLEX RECEPTACLE 20A, 125V, TAMPER PROOF WITH MATCHING PLATE FURNISHED W/ OUTLET. FLUSH MOUNTED 45" AFF EXCEPT AS NOTED.
- R — REFRIGERATOR DUPLEX RECEPTACLE, 20A, 125V SPEC GRADE GROUNDING TYPE, TAMPER PROOF AND MATCHING PLATE. MOUNT RECEPTACLE AT 48 INCHES ABOVE FINISHED FLOOR.
- RANGE OUTLET 50 AMP, 250 VOLT, GROUNDING TYPE FLUSH MOUNTED 18" AFF
- DRYER OUTLET 30 AMP, 250 VOLT, GROUNDING TYPE FLUSH MOUNTED 18" AFF
- RACEWAY & WIRING OR MC CABLE RUN CONCEALED IN WALLS/CEILINGS
- RACEWAY & WIRING RUN EXPOSED
- RACEWAY & WIRING RUN CONCEALED UNDER FLOOR OR BURIED 30" BELOW FINISH GRADE
- HP-XX — HOME RUN TO PANEL, WITH PANEL AND CIRCUIT NUMBER

BRANCH CIRCUIT WIRING SHALL CONSIST OF (1)1/2"C-2*12AWG+1*12GND UNLESS OTHER WISE NOTED. (*)ASTERISK DENOTED *10AWG FOR ALL CIRCUITS CONTAINED IN HOME RUN. (**)DOUBLE ASTERISK DENOTES (1)3/4"C-2*8AWG+1*10GND.

PROVIDE EQUIPMENT GROUNDS IN ACCORDANCE WITH NFPA 70, ARTICLE 250.

- TV — TV OUTLET LOCATION, CABLE AND JACKS BY EC
- TELEPHONE JACK, MOUNT 18"AFF UNLESS NOTED OTHERWISE, RUN ONE CAT 5E CABLE BACK TO TBB.
- DT, PIR, MS — CEILING MOUNTED MOTION SENSOR (WATTSTOPPER OR EQUAL) CORRIDORS: WT-2255 SENSOR & B120E-P POWER PACK. OTHER COMMON SPACES: WT-605 SENSOR & B120E-P POWER PACK. SENSORS AND RELAYS TO CONTROL CIRCUITS IN SPACES INDICATED. DEVICES SHALL PROVIDE FULL COVERAGE IN AREAS INSTALLED.
  DT INDICATES DUAL TECHNOLOGY
  PIR INDICATED PASSIVE INFRARED TECHNOLOGY
- MS — WALL MOUNTED MOTION SENSOR. MOUNT AT 120" AFF UNLESS OTHER WISE NOTED
- S_3 S_4 / S_3 S — SINGLE POLE SWITCH, 120V, 20A, SPEC GRADE, GROUNDING TYPE, MOUNT 48" AFF, 3-3-WAY, 4-4-WAY, LOWER CASE LETTER INDICATES FIXTURE OR CONTROLLED LOAD.
- D_3 D_4 / D_3 D — SINGLE POLE DIMMER SWITCH, 120V, 20A, SPEC GRADE, GROUNDING TYPE, MOUNT 48" AFF, 3-3-WAY, 4-4-WAY, LOWER CASE LETTER INDICATES FIXTURE OR CONTROLLED LOAD.
- SB, SD — SMOKE DETECTOR, PHOTOELECTRIC TYPE, WITH SOUNDER BASE
- CO — CARBON MONOXIDE DETECTOR, WITH SOUNDER BASE
- SELF CONTAINED EMERGENCY LIGHT W/2 HEADS DUAL-LITE (LED) MODEL LZ65I-03L, 65 WATTS FOR 90 MINUTES, COLOR BY ARCHITECT
- EXIT LIGHT FIXTURE, UNSWITCHED, DUAL-LITE LX-U-R-W-E OR APPROVED EQUAL
- A, D, F — LIGHTING FIXTURES, CAPITAL LETTERS DENOTE TYPE PER LIGHTING FIXTURE SCHEDULE. LOWER CASE LETTERS INDICATE SWITCH CONTROL. "ab" INDICATES INBOARD LAMPS CONTROLLED BY OUTBOARD SWITCHED "a" AND "b". DIAGONAL INDICATED NIGHT LIGHT (UNSWITCHED)

UNIT FIRE ALARM NOTES:

1. WHEN UNIT SMOKE DETECTOR GOES INTO ALARM ALL SINGLE STATION DEVICES WITHIN THAT UNIT WILL ACTIVATE.
2. INTERCONNECT ALL 120 VOLT SINGLE STATION SMOKE DETECTORS WITHIN EACH LIVING UNIT. ALL INTERCONNECTED SMOKE DETECTORS SHALL BE ON THE SAME CIRCUIT FOR PROPER OPERATION. REFER TO MANUFACTURER'S INSTALLATION MANUAL AND MOUNT DETECTORS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.
3. CARBON MONOXIDE DETECTORS (120V) IN RESIDENCES SHALL BE INSTALLED AT LEAST 10 FEET FROM ANY HEAT SOURCE.
4. INTERCONNECT ALL 120 VOLT CARBON MONOXIDE (CO) DETECTORS WITHIN EACH LIVING UNIT. ALL INTERCONNECTED CO DETECTORS SHALL BE ON THE SAME CIRCUIT FOR PROPER OPERATION. REFER TO MANUFACTURER'S INSTALLATION MANUAL AND MOUNT DETECTORS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS. CO DETECTORS SHALL HAVE AN ALARM SOUND THAT IS DIFFERENT THAN THE LIVING UNIT SMOKE DETECTORS AND FIRE ALARM SYSTEM ALARMS.
5. AUDIBLE ALARM Db LEVELS SHALL COMPLY WIHT NFPA 72.

LIGHTING FIXTURE SCHEDULE

TYPE	MANUFACTURER / MODEL NUMBER	LAMPS (WATTAGE, COLOR TEMP, LUMENS)	DESCRIPTION
B1	PROGRESS *P8071-28-35K-L10-STR2	LED / 12W / 3000K / 1037 LUMENS	6" DIA LED DOWNLIGHT W/FROSTED POLYCARBONATE LENS, WHITE TRIM AND INTEGRAL ELECTRONIC DIMMING DRIVER, UL LISTED FOR WET LOCATIONS
B2	PROGRESS *P8046-28-30K	LED / 9W / 3000K / 642 LUMENS	5.2" DIA LED ADJUSTABLE ACCENT LIGHT W/DIFFUSED POLYCARBONATE LENS, SATIN WHITE FINISH AND INTEGRAL ELECTRONIC DIMMING DRIVER, UL LISTED FOR WET LOCATIONS
C1	PROGRESS *P8022-28-30K	LED / 17W / 3000K / 1050 LUMENS	7.25" DIA x 1.7" H LED SURFACE MTD SHOWER LIGHT W/DIFFUSED POLYCARBONATE LENS, DIE CAST ALUMINUM HOUSING, WHITE TRIM AND INTEGRAL ELECTRONIC DIMMING DRIVER, UL LISTED FOR WET LOCATIONS
C2	PROGRESS *P8147-28-30K	LED / 16.4W / 3000K / 1035 LUMENS	7.25" DIA x 2.35" H SURFACE MTD CAST ALUMINUM LED LIGHT W/7" DIA DROPPED DECORATIVE GLASS RING, DIFFUSED POLYCARBONATE LENS, WHITE HOUSING FINISH AND INTEGRAL ELECTRONIC DIMMING DRIVER, UL LISTED FOR WET LOCATIONS
C3	PROGRESS *P350007-009-30	LED / 28W / 3000K / 2409 LUMENS	15" DIA x 5-7/8" H SURFACE MTD LED LIGHT W/ETCHED WHITE LINEN GLASS BOWL, BRUSHED NICKEL STEEL HOUSING AND DECORATIVE ACCENT AND INTEGRAL ELECTRONIC DIMMING DRIVER, UL LISTED FOR DAMP LOCATIONS
C4	PROGRESS *P350005-009-30	LED / 21W / 3000K / 1601 LUMENS	SIMILAR TO TYPE C3 EXCEPT 11" DIA x 4-5/8" H WITH LOWER LIGHT OUTPUT
C5	PROGRESS *P3648-3130K9	LED / 17W / 3000K / 1211 LUMENS	9-1/2" DIA x 4-3/8" H SURFACE MTD LED LIGHT W/FROSTED IMPACT RESISTANT POLYCARBONATE DIFFUSER, BLACK CAST ALUMINUM AND INTEGRAL ELECTRONIC DIMMING DRIVER, UL LISTED FOR WET LOCATIONS
C6	PROGRESS *P3910-3030K9	LED / 17W / 3000K / 1211 LUMENS	9" DIA x 4-3/8" H SURFACE MTD LIGHT W/ETCHED OPAL WHITE ACRYLIC DIFFUSER, WHITE STEEL HOUSING AND INTEGRAL ELECTRONIC DIMMING DRIVER, UL LISTED FOR DAMP LOCATIONS
E1	PROGRESS *PE2EU-30	LED / .56W	9" W x 4" T x 2.75" D WALL MTD WHITE THERMOPLASTIC EMERGENCY LIGHT WITH FULLY ADJUSTABLE LAMP HEADS AND NICKEL CADMIUM BATTERY RATED FOR 90 MINS UPON LOSS OF NORMAL POWER, UL LISTED FOR DAMP LOCATIONS
L1	PROGRESS *P7186-30EB	(2) F32T8 / 32W	48" L x 7-3/4" W x 3" H SURFACE MTD FLUORESCENT W/CLEAR PRISMATIC ACRYLIC LENS, WHITE STEEL HOUSING AND END CAPS AND ELECTRONIC NON-DIMMING BALLAST, UL LISTED FOR DAMP LOCATIONS
R1	PROGRESS *P5042-09	(1) A19 BASE, LED EQUIVALENT TO 100W MAX	DECORATIVE SINGLE STEM MTD PENDANT LIGHT W/6" DAI x 8" H ETCHED GLASS CONE, BRUSHED NICKEL STEEL STEM, TRIM AND CANOPY, OVERALL HEIGHT OF 64", UL LISTED FOR DRY LOCATIONS
R2	PROGRESS *P4621-09	(3) A19 BASE, LED EQUIVALENT TO 100W MAX	DECORATIVE 3-LIGHT CHANDELIER W/7-3/16" DIA x 5-3/8" H ETCHED GLASS SHADES, BRUSHED NICKEL STEEL TRIM, ACCENTS AND CANOPY, 9 GUAGE CHAIN, OVERALL DIAMETER OF 23", OVERALL FIXTURE HEIGHT OF 20-1/8", OVERALL HEIGHT W/CHAIN 95", UL LISTED FOR DRY LOCATIONS
R3	PROGRESS *P5300-09	(1) A19 BASE, LED EQUIVALENT TO 100W MAX	DECORATIVE SINGLE CHAIN MTD PENDANT LIGHT W/7-1/2" DAI x 5-3/8" H ETCHED GLASS SHADE, BRUSHED NICKEL STEEL TRIM AND CANOPY, 6FT 9 GAUGE CHAIN, UL LISTED FOR DRY LOCATIONS
T1	PROGRESS *P9105-28		96" L x 1-1/8" W x 7/8" H SURFACE MTD SINGLE CIRCUIT WHITE ALUMINUM TRACK, UL LISTED FOR DRY LOCATIONS
T1	PROGRESS *P9200-28	PAR20 / 50W	3-1/2" DIA x 7-5/8" H TRACK MTD ACCENT LIGHT W/358 DEG HORIZONTAL ROTATION, SELF LOCKING PIVOT FOR VERTICAL POSITIONING, WHITE STEEL HOUSING, AND BLACK BAFFLE, UL LISTED FOR DRY LOCATIONS, PROVIDE 4 FIXTURES PER 8FT TRACK LENGTH
U1	PROGRESS *P7012-30	LED / 6.5W / 3000K / 284 LUMENS	12" L x 3-1/2" W x 1" H UNDERCABINET LED LIGHT W/WHITE ALUMINUM HOUSING, TEMPERED MICRO-PRISMATIC GLASS LENS AND INTEGRAL ELECTRONIC NON-DIMMING DRIVER, UL LISTED FOR DAMP LOCATIONS
	PROGRESS *P8740		UNDERCABINET LIGHT DIRECT WIRE JUNCTION BOX
	PROGRESS *PP8735(6"), P8733(12"), P8737(18"), P8743(24")		6", 12", 18", 24" LONG LINKING CABLE, PROVIDE AS NECESSARY
	PROGRESS *P8743		COUPLING CABLE TO CONNECT LINKING CABLES TOGETHER
W1	PROGRESS *P2006-09	(3) A19 BASE, LED EQUIVALENT TO 100W MAX	26-3/4" L x 8-3/4" H x 8-3/4" D 3-LIGHT WALL MOUNTED VANITY LIGHT W/7-1/4" D x 5-3/8" H ETCHED GLASS SHADES, BRUSHED NICKEL STEEL TRIM, CAN BE MTD UP OR DOWN, UL LISTED FOR DAMP LOCATIONS
W2	PROGRESS *P7092-0930K9	LED / 17W / 3000K / 1211 LUMENS	8" W x 10-5/8" H x 4" D LED WALL SCONCE ETCHED OPAL GLASS DIFFUSER WITH BRUSHED NICKEL TRIM, INTEGRAL ELECTRONIC DIMMING BALLAST, UL LISTED FOR DAMP LOCATIONS
W3	PROGRESS *P7201-30WB	F15T8 / 15W	18-1/4" L x 4" W x 1-3/8" H CLG MTD FLUORESCENT LIGHT W/WHITE ACRYLIC DIFFUSER AND WHITE METAL HOUSING, UL LISTED FOR DAMP LOCATIONS
W4	PROGRESS *P560030-031-30	LED / 9W / 3000K / 670 LUMENS	7-1/2" W x 13-1/2" H x 4-3/4" D WALL MTD EXTERIOR SCONCE W/ETCHED OPAL GLASS DIFFUSER AND BLACK ALUMINUM CURVED BACK-FRAME AND INTEGRAL ELECTRONIC DIMMING BALLAST, UL LISTED FOR WET LOCATION
X1	PROGRESS *PETPE	LED / 1.78W	12.6 W x 7.2" H x 2" D UNIVERSAL MOUNTED EXIT SIGN W/WHITE HIGH IMPACT THERMOPLASTIC HOUSING, RED LETTERS AND NICKEL CADNIUM BATTERY RATED TO OPERATE FOR 90MINS UPON LOSS OF NORMAL POWER, PROVIDE DIRECTIONAL ARROWS AS INDICATED ON PLANS, UL LISTED FOR DAMP LOCATIONS.

ALL LIGHTING FIXTURES SHALL BE ENERGY STAR RATED OR HAVE HIGH PERFORMANCE BALLASTS AND LED LAMPS.

Reviewed for Code Compliance
Inspections Division
Portland, Maine
Date: 12/07/17

Ella Housing
77-79 Congress Street

BRIBURN
architecture for life
28 Maple St | Suite 202 | Portland, ME 04101 | 207-774-8482

CONSULTANTS:

PROJECT NO:	1706
ISSUED:	08/16/17
DRAWN BY:	JLC
CHECKED BY:	WSB
SHEET TITLE:	BASEMENT AND 1ST FLOOR ELECTRICAL PLANS

A-E101