1 FIRST FLOOR FINISH PLAN
3/8" = 1'-0"

2 SECOND FLOOR FINISH PLAN
3/8" = 1'-0"

FINISH SCHEDULE

Room #	Name	Floor	Base	Wall Finish West	Wall Finish North	Wall Finish East	Wall Finish South	Ceiling	Crown	Comments
001	BASEMENT	EX - F8						NONE		
101	ENTRY	EX - F3	EX	EX - W2	EX - W2	EX - W2	EX - W2	EX - C1		
102	KITCHEN	EX - F1	NEW	EX - W2	NEW - W3	EX - W2	EX - W2	NEW - C2	EX	
103	DINING ROOM	EX - F3	EX	NEW - W3	EX - W2	EX - W2	NEW - W3	NEW - C2	EX	
104	LIVING ROOM	EX - F3	EX	EX - W2	EX - W2	EX - W2	EX - W2	NEW - C2	EX	
201	HALL	EX - F3	EX	NEW - W3	EX - W2	EX - W2	NEW - W3	NEW - C2		
202	BATHROOM	NEW - F5	NEW	NEW - W3	NEW - W3	NEW - W3	NEW - W3	NEW - C2		
203	BEDROOM 1	EX - F4	NEW	EX - W2	NEW - W3	NEW - W3	NEW - W3	NEW - C2		
204	CLOSET 1	EX - F4	NEW	EX - W2	NEW - W3	NEW - W3	EX - W2	NEW - C2		
205	BEDROOM 2	EX - F4	NEW	NEW - W3	NEW - W3	EX - W2	EX - W2	NEW - C2		
206	CLOSET									
207	LAUNDRY	NEW - F5	NEW	EX - W2	EX - W2	EX - W2	NEW - W3	NEW - C2		

FINISH LEGEND

WALL

W1 PLASTER
W2 PLASTER + PAINTED WALLPAPER
W3 GYPSUM WALL BOARD
W4 PAINTED WOOD WAINSCOTT
W5 CERAMIC TILE

CEILING

C1 PLASTER
C2 GYPSUM WALL BOARD ON STRAPPING
C3 GYPSUM WALL BOARD ON FURRING & SOUND ISOLATION CLIPS

FLOOR

F1 CLEAR FINISH HARDWOOD
F2 PAINTED HARDWOOD
F3 CLEAR FINISH SOFTWOOD
F4 PAINTED SOFTWOOD
F5 PORCELAIN TILE
F6 CARPET
F7 LAMINATE
F8 CONCRETE

Reviewed for Code Compliance
Inspections Division
Portland, Maine

Date: 12/07/17

LICENSED ARCHITECT
HARRY W. HEPBURN
No. 3316
STATE OF MAINE

ELLA HOUSING - 77 REAR

77 REAR, CONGRESS ST, PORTLAND, ME

RENOVATIONS

BRIBURN architecture for life
28 Maple St. Suite 202, Portland, ME 04101
207-774-0402

CONSULTANTS:

REVISIONS:

No.	Name	Date

ISSUED FOR PERMITING

ISSUED: 10/13/2017
PROJECT No: 1706
DRAWN BY: RIP
CHECKED BY: HH

SHEET TITLE:
FINISH PLANS & SCHEDULE

B-A502