FOUNDATION PLAN

SCALE 1/4"=1'-0"

NOTES:

1. ALL FOOTINGS ARE 10" DEEP 1'-8" WIDE x CONT. WITH (2) # 4 BARS LONGITUDINAL, AND #4 CROSS TIES @ 32" O.C. TYP. UNO
2. STEP IN TOP OF FOUNDATION WALL IS INDICATED THUS: , AND SHOWS LOWER SIDE OF WALL.
3. SEE S1.1 FOR STRUCTURAL GENERAL NOTES
4. FOOTING TO BEAR 4'-6" MIN BELOW GRADE T.O. FOOTINGS ARE INDICATED THUS: (XX'-XX")
5. STEP IN TOP OF FOOTING IS INDICATED THUS: , AND SHOWS LOWER FOOTING.
6. ALL DIMENSIONS TO BE FIELD VERIFIED - CORRELATE W/ EXISTING CONDITIONS.

STATE OF MAINE
AARON C. JONES
No. 10968
LICENSED
PROFESSIONAL ENGINEER
12/16/14

Structural Integrity
Consulting Engineers, Inc.
77 Oak Street
Portland, ME, 04101
p. 207-774-4614
f. 866-793-7835
www.structuralintegr.com

BUILD WITH CONFIDENCE

©2014 Structural Integrity Consulting Engineers, Inc.

S# 14-0177

Reviewed for Code Compliance
Inspection Services
Portland, Maine
Date: 03/04/15

MARK MUELLER ARCHITECTS
A.I.A.
100 Commercial Street
Suite 205
Portland, Maine 04101
Phone: 207.774.9057
Fax: 207.773.3851
Email:
mark@muellerarchitects.com

©COPYRIGHT
MUELLER ARCHITECTS, LLC

RENOVATORS OF:

HARKLEROAD RESIDENCE

47 HOWARD STREET
PORTLAND, MAINE 04101

FOUNDATION PLAN

REVISIONS	DATE
1. Dec. 16th, 2014 FOR PERMIT	Dec. 16th, 2014

PROJECT: HARKLEROAD RESIDENCE

DRAWN BY: WMc

CHECK BY: ACJ

S1.1