Inspections Division
Date: 03/31/14

PRINTED: Feb 12, 2014

FOOTING SCHEDULE				
TYPE	LENGTH	WIDTH	DEPTH	REINFORCING
F2	2'-0"	2'-0"	1'-0"	(3)-#5's BOTT, EW
F3	3'-0"	3'-0"	1'-0"	(4)-#5's BOTT, EW

NOTES:
1. SEE S200 FOR TYPICAL SLAB-ON-GRADE AND TYPICAL WALL REINFORCING DETAILS.
2. REFERENCE EXISTING SLAB ON GRADE ELEVATION = 100'-0"
3. TOP OF CONCRETE ELEVATIONS ARE NOTED (+X") FROM SLAB-ON-GRADE ELEVATION.
4. TOP OF FOOTING ELEVATIONS ARE NOTED [-X'-X"].
5. 'F#' DENOTES FOOTING SIZE, SEE FOOTING SCHEDULE, THIS DWG FOR ADD'L INFORMATION
6. CONTRACTOR TO VERIFY ALL DIMENSIONS, ELEVATIONS AND EXISTING CONDITIONS IN FIELD PRIOR TO CONSTRUCTION AND NOTIFY ENGINEER OF ANY DISCREPANCIES.

PLAN LEGEND
- SHEAR WALL
- BEAM
- HSS COLUMN
- COLUMN FROM ABOVE
- COLUMN BELOW
- COLUMN ABOVE AND BELOW
- HOLD-DOWN

FOUNDATION PLAN

SCALE: 1/4"=1'-0"

1

CASCO BAY ENGINEERING
424 Fore Street
Portland, ME 04101
Phone 207.842.2800
Fax 207.842.2828
www.cascobayengineering.com

CLIENT:
WHIPPLE-CALLENDER ARCHITECTS
136 PLEASANT AVE
PORTLAND, ME 04103

STATE OF MAINE
ERIC DUBE
No. 12630
LICENSED
PROFESSIONAL ENGINEER

32 TURNER ST
32 TURNER ST PORTLAND, ME
BUILDING RENOVATION

ISSUED

No.	DESCRIPTION	DR. BY	CKD. BY	DATE
A	ISSUED FOR PERMIT ONLY-NOT FOR CONSTRUCTION	SJP	ED	2-12-14

SHEET TITLE:
FOUNDATION PLAN

DESIGNED:	SJP
DRAWN:	SJP
DATE:	1-15-14
PROJECT NUMBER:	14-003

S100