Inspections Division
Date: 03/31/14

TYPICAL SLAB-ON-GRADE

NOTES:
1. SAW CUT ¼ OF SLAB THICKNESS, TYP.
2. SPACE CONTROL JOINTS 8–12 FT APART & PERP. TO EACH OTHER.
3. PROVIDE (2) #4x3'–0" AT ALL RE–ENTRANT CORNERS

CONTROL JOINT

CONSTRUCTION JOINT

TYPICAL SLAB-ON-GRADE DETAILS

SCALE: NTS | 1

DETAIL @ WALL CORNER
W/ SINGLE ROW OF WALL REINFORCING

DETAIL @ WALL INTERSECTION
W/ SINGLE ROW OF WALL REINFORCING

DETAIL @ WALL END
W/ SINGLE ROW OF WALL REINFORCING

NOTE:
PLACE @ 40'–0"o.c. MAX. OR AS SHOWN ON FDN PLAN. DO NOT LOCATE JOINT WITHIN 3'–0" OF ANY GRID LINE OR BUILDING CORNER.

CONSTRUCTION JOINT DETAIL
W/ SINGLE ROW OF WALL REINFORCING

TYPICAL FOUNDATION WALL DETAILS

SCALE: NTS | 2

SECTION

SCALE: 3/4"=1'-0" | 3

SECTION

SCALE: 3/4"=1'-0" | 4

TYPICAL BASEPLATE DETAIL

SECTION

SCALE: 3/4"=1'-0" | 5

SECTION

SCALE: 3/4"=1'-0" | 6

SECTION

SCALE: 3/4"=1'-0" | 7

SECTION

SCALE: 3/4"=1'-0" | 8

SECTION

SCALE: 3/4"=1'-0" | -

SECTION

SCALE: 3/4"=1'-0" | -

SECTION

SCALE: 3/4"=1'-0" | -

SECTION

SCALE: 3/4"=1'-0" | -

CASCO BAY ENGINEERING
424 Fore Street
Portland, ME 04101
Phone 207.842.2800
Fax 207.842.2828
www.cascobayengineering.com

CLIENT:
WHIPPLE-CALLENDER ARCHITECTS
136 PLEASANT AVE
PORTLAND, ME 04103

STATE OF MAINE
ERIC DUBE
No. 12630
LICENSED
PROFESSIONAL ENGINEER

32 TURNER ST
32 TURNER ST
PORTLAND, ME
BUILDING RENOVATION

ISSUED

No.	DESCRIPTION	DR. BY	CKD. BY	DATE
A	ISSUED FOR PERMIT ONLY-NOT FOR CONSTRUCTION	SJP	ED	2-12-14

SHEET TITLE:
CONCRETE DETAILS

DESIGNED:	SJP
DRAWN:	SJP
DATE:	1–15–14
PROJECT NUMBER:	14–003

S200

PRINTED: Feb 12, 2014