

Window and door schedule

High-Performance Little House

10/11/2017

| <u>door</u> | <u>location</u> | <u>operable?</u> | | <u>width</u> [in] | <u>height</u> [in] | <u>width</u> [mm] | <u>height</u> [mm] | <u>f2</u> | <u>= height from FF</u> | <u>egress?</u> |
|--------------------|-----------------|------------------|--|----------------------|-----------------------|----------------------|-----------------------|-----------|-------------------------|----------------|
| Front door | Southwest | Y | | 34 | 82 | 864 | 2,083 | 19.4 | n/a | YES |
| Sliding door | Southeast | Y | | 71 | 82 | 1,800 | 2,080 | 40.3 | n/a | |
| Interior bathroom: | ground floor | Y | | 32 | 80 | 813 | 2,032 | 17.8 | n/a | |
| Interior bathroom: | second floor | Y | | 30 | 80 | 762 | 2,032 | 16.7 | n/a | |

| <u>window</u> | <u>location</u> | <u>operable?</u> | <u>hinges</u> | <u>width</u> [in] | <u>height</u> [in] | <u>width</u> [mm] | <u>height</u> [mm] | <u>f2</u> | <u>height from FF</u> [in] | <u>egress?</u> | |
|---|--|------------------|---------------|----------------------|-----------------------|----------------------|-----------------------|-----------|-------------------------------|----------------|-----|
| <p><i>Intus Arcade uPVC window, triple glaze</i></p> <p><i>All operable units shall be tilt-turn</i></p> <p><i>Only windows with operable area > 5.7 sq ft shall be considered egress</i></p> <p><i>Include screens for operable windows</i></p> <p><i>Include nailing flange for all windows</i></p> <p><i>Include exterior frame color (TBD)</i></p> <p><i>Interior of frame white</i></p> | Gnd floor picture | N | n/a | 76 | 57 | 1,930 | 1,448 | 30.1 | 24" | | |
| | <p>overall dimensions shown this window is a duplet with Reinforced integral mullion</p> | | | | | | | | | | |
| | Ascending stairs | N | n/a | | 26 | 26 | 660 | 660 | 4.7 | 68" | |
| | Dining area (NE) | TT | right | | 32 | 40 | 813 | 1,016 | 8.9 | 40" | |
| | 1ST fl Bath (NW) | TT | right | | 26 | 34 | 660 | 864 | 6.1 | 48" | |
| | 2ND fl Bath (NE) | TT | right | | 26 | 34 | 660 | 864 | 6.1 | 48" | |
| | 2ND fl lounge (NW) | TT | right | | 32 | 50 | 813 | 1,270 | 11.1 | 32" | YES |
| | 2ND fl lounge 1 (SW) | TT | right | | 32 | 50 | 813 | 1,270 | 11.1 | 32" | YES |
| 2ND fl lounge 1 (SW) | TT | right | | 32 | 50 | 813 | 1,270 | 11.1 | 32" | YES | |
| 2ND fl lounge 1 (SW) | TT | right | | 32 | 50 | 813 | 1,270 | 11.1 | 32" | YES | |
| 2ND fl BR 1 (SE) | TT | right | | 32 | 50 | 813 | 1,270 | 11.1 | 32" | YES | |
| 2ND fl BR 2 (SE) | TT | right | | 32 | 50 | 813 | 1,270 | 11.1 | 32" | YES | |