

Window and door schedule

High-Performance Little House

11/10/2017

<u>door</u>	<u>location</u>	<u>operable?</u>		<u>width</u> [in]	<u>height</u> [in]	<u>width</u> [mm]	<u>height</u> [mm]	<u>f2</u>	= <u>height from FF</u>	<u>egress?</u>	
Front door	Southwest	Y		34	82	864	2,083	19.4	n/a	YES	
Sliding door	Southeast	Y		71	82	1,800	2,080	40.3	n/a		
Interior bathroom:	ground floor	Y		32	80	813	2,032	17.8	n/a		
Interior bathroom:	second floor	Y		30	80	762	2,032	16.7	n/a		
<u>window</u>	<u>location</u>	<u>operable?</u>	<u>hinges</u>	<u>width</u> [in]	<u>height</u> [in]	<u>width</u> [mm]	<u>height</u> [mm]	<u>f2</u>	<u>height from FF</u> [in]	<u>egress?</u>	
<i>Intus Arcade uPVC window, triple glaze</i> <i>All operable units shall be tilt-turn</i> <i>Only windows with operable area > 5.7 sq ft shall be considered egress</i> <i>Include screens for operable windows</i> <i>Include nailing flange for all windows</i> <i>Include exterior frame color (TBD)</i> <i>Interior of frame white</i>	Gnd floor picture	N	n/a	76	57	1,930	1,448	30.1	24"		
	overall dimensions shown this window is a duplet with Reinforced integral mullion										
	Ascending stairs	N	n/a	26	26	660	660	4.7	68"		
	Dining area (NE)	Y	right	32	40	813	1,016	8.9	40"		
	1ST fl Bath (NW)	Y	right	26	34	660	864	6.1	48"		
	2ND fl Bath (NE)	Y	right	26	34	660	864	6.1	48"		
	2ND fl lounge (NW)	Y	right	32	50	813	1,270	11.1	32"	YES	
	2ND fl lounge 1 (SW)	Y	right	32	50	813	1,270	11.1	32"	YES	
	2ND fl lounge 1 (SW)	Y	right	32	50	813	1,270	11.1	32"	YES	
	2ND fl lounge 1 (SW)	Y	right	32	50	813	1,270	11.1	32"	YES	
2ND fl BR 1 (SE)	Y	right	32	50	813	1,270	11.1	32"	YES		
2ND fl BR 2 (SE)	Y	right	32	50	813	1,270	11.1	32"	YES		