

75 Quebec Street Interior Alteration Attachment
Description/scope of work

First Floor Front Unit Current Layout. Schematic #1: Remove cracked plaster and Sheetrock on walls and ceilings, remove floor tiling in bath and kitchen, remove old carpet, remove cabinets, counters, and fixtures in bath and kitchen. Remove 10' of non load bearing wall in back hall. See drawing for notation. (A)

First Floor Back Unit Current Layout. Schematic #2: Remove cracked plaster and Sheetrock on walls and ceilings, remove floor tiling in bath and kitchen, remove cabinets, counters, and fixtures in bath and kitchen. Remove 10' feet of non load bearing wall in kitchen. See drawing for notation. (B)

Second Floor Front, Back, and Top Floor Unit Current Layout. Schematic 's #3, 4, & 5: Remove cracked plaster and Sheetrock on walls and ceilings, remove Floor tiling in bath and kitchen, remove cabinets, counters and fixtures in bath and kitchen. Remove 9' of non load bearing wall in kitchen. See drawing for notation. (C)

ALL DRAWINGS ARE TO SCALE. ONE SQUARE EQUALS ONE FOOT