FOUNDATION PLAN

1/4"=1'-0"

NOTES:

1. TOP OF FOOTING EL 96'-0" U.N.O.
2. TOP OF WALL EL 100'-0" U.N.O.
3. BP- INDICATES STEEL BASE PL, SEE DETAILS ON S3.1.
4. P- INDICATES CONC PIER, SEE DETAIL ON S2.1
5. F- INDICATES SPREAD FOOTING, SEE SCHEDULE THIS DWG.
6. BF- INIDCATES STEEL BRACED FRAME, SEE ELEVATION THIS DWG.

FOOTING SCHEDULE		
MARK	SIZE	REINF
F3	3'-0"x3'-0"x1'-0"	4#5 E.W.B.
F4	4'-0"x4'-0"x1'-0"	5#5 E.W.B.
F47	4'-0"x7'-0"x1'-0"	5#5 L.W.B. & 8#5 S.W.B.

BF-1 ELEVATION

NOT FOR CONSTRUCTION
PERMIT SET 10/3/2014

THESE DWGS ARE NOT COMPLETE. DESIGN IS STILL IN PROGRESS. CONTRACTOR SHALL CARRY APPROPRIATE CONTINGENCY.

THIS DRAWING IS AN INSTRUMENT OF SERVICE AND SHALL REMAIN THE PROPERTY OF BECKER STRUCTURAL ENGINEERS INC. IT SHALL NOT BE REPRODUCED, COPIED, LENT OR DISPOSED OF DIRECTLY OR INDIRECTLY NOR USED FOR ANY PURPOSE OTHER THAN FOR WHICH IT IS SPECIFICALLY FURNISHED AND MUST BE RETURNED TO BECKER STRUCTURAL ENGINEERS INC. ON COMPLETION OF WORK, IF REQUESTED.

CITY OF PORTLAND, MAINE · RESURGAM
Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 12/08/14

BECKER STRUCTURAL
75 York Street,
207.879.1838

STATE OF MAINE
NATHAN R. MERRILL
No. 12279
PROFESSIONAL ENGINEER

Rev. No	Date	Issued For	Appvd

BRAMLEY/SIMMONS RESIDENCE
PORTLAND, ME

FOUNDATION PLAN

Designed NRM	Scale NOTED
Drawn MSK	Date 10/3/14
Checked PBB	Becker Job Number 3354

S1.1