



Enertec Heating Cooling and Electrical

Po Box 8709
 Portland, ME 04104
 United States
 (207)776-4614
 Justin@enertecme.com
 www.enertecme.com

ESTIMATE

ADDRESS

Thomas Seekins
 Melbourne St.
 Portland, ME

ESTIMATE # 1045

DATE 05/17/2016

ACTIVITY	QTY	RATE	AMOUNT
Materials & Installation 1st floor: -Install 1 Daikin DAI2MXS18NMVJU 36,000 BTU outdoor condensing unit with rain hood . -Install 1 Daikin DAIFVXS18NVJU 18,000 BTU indoor floor mount unit in living/common area. -Install 2 Daikin DAIFVXS09NVJU 9,000 BTU indoor floor mount units in bedrooms 1 & 2 -price includes quick sling stand, line sets, condensate drains, and all electrical feeds from indoor units to outdoor condensing unit. 2nd floor: -Install one Daikin DAI4MXS36NMVJU 36,000 BTU Outdoor condensing unit with rain hood. -Install one Daikin DAIFVXS18NVJU 18,000 BTU indoor floor mount unit in Living/common area. -Install Two Daikin DAIFVXS09NVJU 9,000 BTU indoor floor mount units in bedrooms 1 & 2. -price includes quick sling stand, line sets, condensate drains, and all electrical feeds from indoor units to outdoor condensing unit. 3rd floor: Will be tied in with second floor electrical panel -Install one Daikin DAI2MXS18NMVJU 18,000 BTU Outdoor condensing unit with rain hood. -Install 1 Daikin DAIFTXS18LVJU 18,000 BTU indoor head unit in on 3rd floor bonus space. -Install one Daikin DAIFVXS09NVJU 9,000 BTU indoor floor mount unit on 3rd floor bonus space. -Install one Daikin DAIFTXS09LVJU 9,000 BTU indoor wall mount head unit in front hallway. -price includes wall bracket, line sets, condensate drains, and all electrical feeds from indoor units to outdoor condensing unit.	1	22,371.60	22,371.60
Warranty All Daikin equipment will come with a 12 year manufactures parts warranty. Daikin also offers the Asure program for an additional cost which covers the cost of labor on any repairs for 10 years.	1	0.00	0.00
Rebate Each Condo qualifies for an efficiency Maine rebate of 500.00 for installing high efficient Heat Pumps	1	-1,000.00	-1,000.00
Customer Responsibilities Customer is responsible for electrical disconnects going to each outdoor condensing unit. Enertec will work with the electrical Contractor on any info they need. Enertec will hook the unit up from the disconnect.	1	0.00	0.00

Thank you for the opportunity!

TOTAL

\$21,371.60

Please call with any questions

Accepted By

Accepted Date