



1 Roof & Rooftop Equipment Plan
 1/4" = 1'-0"



- Note 1: Coordinate mechanical unit weights, curb dims., & roof openings with mechanical unit supplier & Contractor.
- Note 2: Fasten 4x6 P.T. & (2) 2x6 P.T. sub-curbs to top chord of steel joist with a 1/2" diam. HDG thru-bolt within 6" from all unit corners. Extend bolt between angles in top chord - See Section 1/S-2.
- Note 3: Provide (2) 2x6 P.T. sub-curbs flush with interior face of lt. ga. unit curb. See Note 2. Locate all four corners of unit curb for each fan on top chord panel point of existing stl. joists. - typical.
- Note 4: Locate 4x6 curb centered on top chord panel point of exist. steel joist on this side of RTU.

90 CONGRESS STREET RESTAURANT / Roof Equip. & Framing Plan

90 Congress Street, Portland, Maine 04101 December 16, 2013

Reiter Architecture & Design / PO Box 275 / Brooklin ME 04616 / 207-359-2300 / laurenjreiter@yahoo.com
 L & L Structural Engineering Services, Inc. / 6 Q Street / South Portland ME 04106 / 207-767-4830



S-1