

TYPICAL WALL AND CEILING ASSEMBLIES

TYPICAL EXTERIOR WALL ASSEMBLY (WHERE EXPOSED) R-14
 5/8" GWP
 EXISTING ROUGH CUT WOOD FRAMING W/
 4" DENSE PACKED CELLULOSE (R-14 MIN)
 EXISTING WOOD SHEATHING
 EXISTING WOOD SIDING

(NOTE: IN RENOVATION TO BE PERMITTED AT A LATER TIME EXTERIOR SIDING WILL BE REMOVED AND RIGID INSULATION WILL BE INSTALLED OUTSIDE EXTERIOR SHEATHING)

TYPICAL INTERIOR WALL
 5/8" GWP
 2X4 WOOD STUD @ 16" O.C. W/
 BATT INSULATION
 5/8" GWP

TYPICAL CEILING ASSEMBLY
 5/8" GWP
 IX WOOD FURRING
 EXISTING JOIST FRAMING
 EXISTING SUB-FLOORING
 FINISH FLOOR TO BE DETERMINED

GENERAL PLAN NOTES

DOORS:

- ALL NEW INTERIOR DOORS TO ROOMS TO BE 2'-6" BY 6'-8" UNO
- ALL NEW EXTERIOR DOORS TO BE 3'-0" X 6'-8" UNO
- CLOSET DOORS TO BE CHOSEN BY OWNER

