COPYRIGHT: Reuse or reproduction of the contents of this document is not permitted without written permission of Bild Architecture LLC

TYPICAL WALL AND CEILING ASSEMBLIES

TYPICAL EXTERIOR WALL ASSEMBLY (WHERE EXPOSED) R-14
5/8" GWB
EXISTING ROUGH CUT WOOD FRAMING W/
4" DENSE PACKED CELLULOSE (R-14 MIN)
EXISTING WOOD SHEATHING
EXISTING WOOD SIDING

(NOTE: IN RENOVATION TO BE PERMITTED AT A LATER TIME EXTERIOR SIDING WILL BE REMOVED AND RIGID INSULATION WILL BE INSTALLED OUTSIDE EXTERIOR SHEATHING.)

TYPICAL INTERIOR WALL
5/8" GWB
2X4 WOOD STUD @ 16" O.C. W/
BATT INSULATION
5/8" GWB

TYPICAL CEILING ASSEMBLY
5/8" GWB
1X WOOD FURRING
EXISTING JOIST FRAMING
EXISTING SUB-FLOORING
FINISH FLOOR TO BE DETERMINED

GENERAL PLAN NOTES

DOORS:
- ALL NEW INTERIOR DOORS TO ROOMS TO BE 2'-6" BY 6'-8" U.N.O.
- ALL NEW EXTERIOR DOORS TO BE 3'-0" X 6'-8" U.N.O.
- CLOSET DOORS TO BE CHOSEN BY OWNER

FIRST FLOOR NOTES:
- INSTALL NFPA 13D SPRINKLER SYSTEM IN FIRST FLOOR CEILING

30 A1.1 FIRST FLOOR
0 8'-0" SCALE: 1/8" = 1'-0"

SECOND FLOOR NOTES:
- INSTALL NFPA 13D SPRINKLER SYSTEM IN SECOND FLOOR CEILING
- ENTIRE SECOND FLOOR CEILING TO BE 1 HOUR FIRE RATED AND RATED FOR AN STC OF 45 (SEE ASSEMBLY ABOVE)

20 A1.1 SECOND FLOOR
0 8'-0" SCALE: 1/8" = 1'-0"

10 A1.1 THIRD FLOOR
0 8'-0" SCALE: 1/8" = 1'-0"

Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 06/26/13

Bild
PO Box
Portland
207.408
evan@b

PROJECT NO. 13006
PROJECT NAME 33 ATLANTIC STREET

DRAWN BY EAC
SHEET TITLE PLANS

ISSUE DATE 6/7/13
SHEET SCALE 1/8"=1'-0"

A
1.1