COPYRIGHT: Reuse or reproduction of the contents of this document is not permitted without written permission of Bild Architecture LLC

CITY OF PORTLAND, MAINE
RESURGAM

Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 06/26/13

## TYPICAL WALL AND CEILING ASSEMBLIES

TYPICAL EXTERIOR WALL ASSEMBLY (WHERE EXPOSED) R-14
5/8" GWB
EXISTING ROUGH CUT WOOD FRAMING W/
4" DENSE PACKED CELLULOSE (R-14 MIN)
EXISTING WOOD SHEATHING
EXISTING WOOD SIDING

(NOTE: IN RENOVATION TO BE PERMITTED AT A LATER TIME EXTERIOR SIDING WILL BE REMOVED AND RIGID INSULATION WILL BE INSTALLED OUTSIDE EXTERIOR SHEATHING.)

TYPICAL INTERIOR WALL
5/8" GWB
2X4 WOOD STUD @ 16" O.C. W/
BATT INSULATION
5/8" GWB

TYPICAL CEILING ASSEMBLY
5/8" GWB
IX WOOD FURRING
EXISTING JOIST FRAMING
EXISTING SUB-FLOORING
FINISH FLOOR TO BE DETERMINED

## GENERAL PLAN NOTES

DOORS:
- ALL NEW INTERIOR DOORS TO ROOMS
  6'-8" U.N.O.
- ALL NEW EXTERIOR DOORS TO BE 3'-
- CLOSET DOORS TO BE CHOSEN BY O

## FIRST FLOOR NOTES:
- INSTALL NFPA 13D SPRINKLER SYSTEM IN FIRST FLOOR CEILING

30 A1 FIRST FLOOR
0 8'-0" SCALE: 1/8" = 1'-0"

## SECOND FLOOR NOTES:
- INSTALL NFPA 13D SPRINKLER SYSTEM IN SECOND FLOOR CEILING
- ENTIRE SECOND FLOOR CEILING TO BE 1 HOUR FIRE RATED AND RATED FOR AN STC OF 45 (SEE ASSEMBLY ABOVE)

20 A1 SECOND FLOOR
0 8'-0" SCALE: 1/8" = 1'-0"

10 A1 THIRD FLOOR
0 8'-0" SCALE: 1/8" = 1'-0"

Bild
PO Box
Portlan
207.40
evan@b

PROJECT NO. 13006
PROJECT NAME 33 ATLANTIC STREET

RE-ISSUED - 6/13/13

DRAWN BY EAC
SHEET TITLE PLANS

ISSUE DATE 6/7/13
SHEET SCALE 1/8"=1'-0"

A

1.1