

SECTION 10550

POSTAL SPECIALTIES (MAILBOXES)

1. GENERAL

1.1 DESCRIPTION OF WORK

- A. Drawings and general provisions of Contract, including General Conditions and Division 1 specifications, apply to work in this section.
- B. The extent of work shall be as shown on Drawings and called for in these Specifications. The work under this section of Specifications includes furnishing and installing the items listed as indicated on Drawings.

2. PRODUCTS:

- 2.1 Mailboxes shall be manufactured by Auth – Florence 1400-53 HAS Series, black, front loading, installed to Postal Regulations. Provide for fifteen (15) mailboxes. Refer to Drawings for configurations per building.
- 2.2 The lock on each compartment door shall be keyed to the resident's door. It shall be a pin tumbler type with spring bolt. Provide Locking Device 2090. Provide a “Key Keeper” by entry door for mailman.

3. EXECUTION:

- 3.1 Mailboxes shall be framed into wall as shown on drawings. Care shall be taken to insure tight fit and that Vertical Placement (Ht. to boxes) meets Postal Regulations. Properly secure, block and align unit as shown in manufacturer's installation guidelines. All work shall be done in first-class manner insuring high-grade finish.
- 3.2 NOTE: The Contractor shall submit drawings on every item specified in this section. There shall be no substitutions without a written explanation from the subcontractor that the specific item is equal with the item specified by the Architect. All substitutions shall be approved by the Architect and the Owner.

END OF SECTION