



SECTION 01045

CUTTING AND PATCHING

1. GENERAL

1.1 REFERENCES

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division 1 Specification sections, apply to work of this Section.
- B. Divisions 2 through 16.

1.2 DESCRIPTION OF WORK

- A. Definition: "Cutting and patching" includes cutting into existing construction to provide for the installation or performance of other work and subsequent fitting and patching required to restore surfaces to their original condition. This section does not apply to new work that has been installed as part of the Work.
- B. Structural Work: Do not cut-and-patch structural work in a manner resulting in a reduction of load-carrying capacity or load/deflection ratio.
- C. Operational/Safety Limitations: Do not cut-and-patch operational elements and safety components in a manner resulting in decreased performance, shortened useful life, or increased maintenance.
- D. Visual/Quality Limitations: Do not cut-and-patch work exposed to view (exterior and interior) in a manner resulting in noticeable reduction of aesthetic qualities and similar qualities, as judged by the Architect/Engineer.
- E. Limitation on Approvals: The Architect/Engineer's approval to proceed with cutting and patching does not waive right to later require removal/replacement of work found to be cut-and-patched in an unsatisfactory manner, as judged by the Architect/Engineer.
- F. Materials marked to be removed and reused shall be repaired as necessary to maintain their existing condition. When repair is not sufficient, existing materials shall be disposed of and new materials installed to match existing materials.
- G. Refer to other sections of these specifications for specific cutting and patching requirements and limitations applicable to individual units of work.
- H. Unless otherwise specified, requirements of this Section apply to Mechanical and Electrical work. Refer to Divisions 15 and 16 for additional requirements and limitations on cutting and patching of mechanical and electrical work.

1.3 QUALITY ASSURANCE



- A. Refer to Section 01631, Products and Substitutions, for general provisions covering product selection, substitutions, material storage and installation.
- B. Refer to Section 01400, Quality Control Services, for provisions for testing and inspections.
- C. Refer to specific Specification Section covering subject in question for quality assurance requirements.

1.4 SUBMITTALS

- A. Issue submittals in accordance with Section 01300, Submittals.
- B. Refer to specific Specification Section covering subject in question for submittal requirements.

2. PRODUCTS

2.1 GENERAL

- A. Use materials for cutting and patching that are identical to existing materials. If identical materials are not available, or cannot be used, use materials that match existing adjacent surfaces to the fullest extent possible with regard to visual effect. Use materials for cutting and patching that will result in equal-or-better performance characteristics.
- B. Fire-stopping:
 - 1. Seal openings in fire-rated walls and floors to make a tight fit with penetrating items, using appropriate non-combustible filler material. to provide a rating equivalent to wall/floor assemble.
 - 2. Acceptable filler materials include:
 - a. Concrete
 - b. Cementitious proprietary product: Zonolite Firestop ZF-1
 - c. Blanket-type mineral-fiber or ceramic-fiber insulation (glass-fiber insulation is not acceptable)
 - d. Fire-resistant sealant: Domtar Fire-Halt, Dow Corning Fire Stop, Hilti CS 240 Firestop, or Nelson CLK or CMP
 - e. Fire-resistant silicone foam: Dow Corning RTV Foam Penetration Seal System, Hilti CB 120 Adhesive Filling and Sealing Foam, Tremco Fyre-Sil
 - f. Flexible intumescent strip wrapped around pipe penetrations: Dow Corning Fire Stop Intumescent Wrap, Hilti CS 24720 Intumescent Wrap, Nelson RSW, Tremco TREMstop WS
 - g. Intumescent fibrous material enclosed in a polyethylene envelope: Nelson PLW, Tremco TREMstop PS
 - h. Pliable intumescent putty: Nelson FSP Flameseal, Tremco TREMstop WBM



- i. Water-based intumescent fire-protective coating for electrical cables: Nelson CTG

3. Neatly patch and seal exposed-to-view openings, using sealants, tooled mortar joints, escutcheons, or flanged collars, as appropriate.

3. EXECUTION

3.1 INSPECTION

- A. Before cutting, examine surfaces to be cut and patched and conditions under which the work is to be performed. If unsafe or otherwise unsatisfactory conditions are encountered, take corrective action before proceeding with the work.

3.2 TEMPORARY SUPPORT

- A. To prevent failure provide temporary support of work to be cut.

3.3 PROTECTION

- A. Protect other work during cutting and patching to prevent damage. Provide protection from adverse weather conditions for that part of the project that may be exposed during cutting and patching operations. Avoid interference with use of adjoining areas or interruption of free passage to adjoining areas.

3.4 PERFORMANCE

- A. Employ skilled workmen to perform cutting and patching work. Except as otherwise indicated or as approved by the Architect/Engineer, proceed with cutting and patching at the earliest feasible time and complete work without delay.
- B. Cutting:
 1. Cut the work using methods that are least likely to damage work to be retained or adjoining work. Provide dust barriers to prevent dust from entering existing building beyond immediate work area. Where possible, review proposed procedures with the original installer; comply with original installer's recommendations.
 2. In general, where cutting is required, use hand or small power tools designed for sawing or grinding, not hammering and chopping. Cut through concrete and masonry using a cutting machine such as a carborundum saw or core drill to insure a neat hole. Cut holes and slots neatly to size required with minimum disturbance of adjacent work. To avoid marring existing finished surfaces, cut or drill from the exposed or finished side into concealed surfaces. Temporarily cover openings when not in use.
 3. Comply with requirements of applicable sections of Division 2 where cutting and patching requires excavating and backfilling.



4. By-pass utility services such as pipe and conduit, before cutting, where such utility services are shown or required to be removed, relocated or abandoned. Cut-off conduit and pipe in walls or partitions to be removed. After by-pass and cutting, cap, valve or plug and seal tight remaining portion of pipe and conduit to prevent entrance of moisture or other foreign matter.

C. Patching:

1. Patch with seams which are durable and as invisible as possible. Comply with specified tolerances for the work.
2. Where feasible, inspect and test patched areas to demonstrate integrity of work.
3. Restore exposed finishes of patched areas and where necessary extend finish restoration into retained adjoining work in a manner which will eliminate evidence of patching and refinishing.
4. Where removal of walls or partitions extends one finished area into another finished area, patch and repair floor and wall surfaces in the new space to provide an even surface of uniform color and appearance. If necessary to achieve uniform color and appearance, remove existing floor and wall coverings and replace with new materials.
5. Where patch occurs in a smooth painted surface, extend final paint coat over entire unbroken surface containing patch, after patched area has received prime and base coat.
6. Patch, repair or rehang existing ceilings as necessary to provide an even plane surface of uniform appearance.

3.5 MAINTENANCE OF TRAFFIC, ACCESS, AND UTILITIES

- A. Maintain accessibility from street at all times to any fire hydrants within construction area. Ensure that utilities serving adjacent buildings remain in service.

END OF SECTION