



SECTION 02225

SELECTIVE DEMOLITION

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes:
 - 1. Procedures for demolition and removal of existing building elements.
 - 2. Removal of designated building equipment and fixtures.

1.2 SYSTEM DESCRIPTION

The extent of Selective Demolition Work is removal of existing building on site.

- A. Demolition shall be such that all construction, new and existing, can be performed, and completed in accordance with the construction documents.
- B. Verify the scope of the Work under this Section including salvage material.

1.3 QUALITY ASSURANCE

- A. Engage only personnel who can demonstrate not less than five years successful experience in Work of similar character.
- B. Performance Criteria:
 - 1. Fire: Do not use means, methods, techniques or procedures which would produce any fire hazard unless otherwise approved by Contracting Officer.
 - 2. Water: Do not use means, methods, techniques or procedures which would produce excessive water run-off, and water pollution.
 - 3. Air Pollution: Do not use means, methods, techniques or procedures which would produce uncontrolled dust, fumes or other damaging air pollution.

1.4 PROJECT SITE

- A. The Contractor shall verify all existing conditions and notify the Contracting Officer of discrepancies before proceeding with the Work.
- B. Condition of Structure: The Owner assumes no responsibility for the actual condition of portions of the structure to be demolished.



- C. Protection: Make sure that the safe passage of persons around the area of demolition is maintained during the demolition operation. Conduct operations to prevent injury to adjacent buildings, structures, other facilities, and persons.

PART 2 - PRODUCTS

2.1 SALVAGED MATERIALS

- A. Removed and salvaged materials of value not designated for reinstallation, unless claimed as salvage by the Owner, shall become the property of the Contractor and shall be removed from the premises by the Contractor.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Verify existing conditions before starting work.
- B. Verification of Conditions: Verify that field measurements, surfaces, substrates and conditions are as required, and ready to receive Work.
- C. Report in writing to the Owner prevailing conditions that will adversely affect satisfactory execution of the Work of this Section. Do not proceed with Work until unsatisfactory conditions have been corrected.
- D. By beginning Work, Contractor accepts conditions and assumes responsibility for correcting unsuitable conditions encountered at no additional cost to the Owner.

3.2 PREPARATION

- A. Provide adequate protection of other work during selective demolition to prevent damage and provide protection of the work from adverse weather exposure.

3.3 PROCEDURE

- A. Employ only skilled tradesmen to perform selective demolition.

3.4 POLLUTION CONTROLS

- A. Use temporary enclosures and other suitable methods to limit the amount of dust and dirt rising and scattering in the air to the lowest practical level.



- B. Comply with governing authorities pertaining to environmental protection.

3.5 DISPOSAL OF DEMOLISHED MATERIALS

- A. Collect, recycle, reuse, and dispose of demolished materials per governing regulatory authorities.

END OF SECTION