

**SECTION 07840
FIRESTOPPING****PART 1 - GENERAL****1.01 RELATED DOCUMENTS**

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification Section, apply to work specified in this section.

1.02 DEFINITIONS

- A. Firestopping: Material or combination of materials used to retain integrity of fire-rated construction by maintaining an effective barrier against the spread of flame, smoke, and hot gases through penetrations in, or construction joints between, fire rated wall and floor assemblies.

1.03 GENERAL DESCRIPTION OF THE WORK OF THIS SECTION

Only tested firestop systems shall be used in specific locations as follows:

- A. Penetrations for the passage of duct, cable, cable tray, conduit, piping, electrical busways and raceways through fire-rated vertical barriers (walls and partitions), horizontal barriers (floor/ceiling assemblies), and vertical service shaft walls and partitions.
- B. Safing slot gaps between edge of floor slabs and curtain walls.
- C. Openings between structurally separate sections of wall or floors.
- D. Gaps between the top of walls and ceilings or roof assemblies.
- E. Expansion joints in walls and floors.
- F. Openings and penetrations in fire-rated partitions or walls containing fire doors.
- G. Openings around structural members which penetrate floors or walls.

1.04 RELATED WORK OF OTHER SECTIONS

- A. Coordinate work of this section with work of other sections as required to properly execute the work and as necessary to maintain satisfactory progress of the work of other sections, including:
 - 1. Section 03 30 00 - Cast-In-Place Concrete
 - 2. Section 04 20 00 - Unit Masonry
 - 3. Section 07 90 00 - Joint Sealants
 - 4. Section 09 20 00 - Plaster and Gypsum Board
 - 5. Section 13 48 00 - Sound, Vibration and Seismic Control
 - 6. Section 21 00 00 - Fire Suppression
 - 7. Section 22 00 00 - Plumbing
 - 8. Section 23 00 00 - Heating, Ventilating, and Air Conditioning (HVAC)
 - 9. Section 26 00 00 - Electrical
 - 10. Section 26 00 00 - Communications



1.05 REFERENCES

- A. Test Requirements: ASTM E 814, "Standard Method of Fire Tests of Through Penetration Fire Stops"
- B. Test Requirements: UL 1479, "Fire Tests of Through-Penetration Firestops"
- C. Test Requirements: UL 2079, "Tests for Fire Resistance of Building Joint Systems"
- D. Underwriters Laboratories (UL) of Northbrook, IL publishes tested systems in their "FIRE RESISTANCE DIRECTORY" that is updated annually.
 - 1. UL Fire Resistance Directory:
 - a. Firestop Devices (XHJI)
 - b. Fire Resistance Ratings (BXRH)
 - c. Through-Penetration Firestop Systems (XHEZ)
 - d. Fill, Voids, or Cavity Material (XHHW)
 - e. Forming Materials (XHKU)
 - f. Joint Systems (XHBN)
 - g. Perimeter Fire Containment Systems (XHDG)
 - 2. Alternate Systems: "Omega Point Laboratories Directory" (updated annually).
- E. Test Requirements: ASTM E 1966, "Standard Test Method for Fire Resistive Joint Systems"
- F. Test Requirements: ASTM E 2307, "Standard Test Method for Determining Fire Resistance of Perimeter Fire Barrier Systems Using Intermediate-Scale, Multi-story Test Apparatus"
- G. Inspection Requirements: ASTM E 2174, "Standard Practice for On-site Inspection of Installed Fire Stops"
- H. ASTM E 84, "Standard Test Method for Surface Burning Characteristics of Building Materials"
- I. International Firestop Council Guidelines for Evaluating Firestop Systems Engineering Judgments
- J. International Building Code (IBC 2009)
- K. NFPA 101 - Life Safety Code
- L. NFPA 70 - National Electric Code

1.06 QUALITY ASSURANCE

- A. Fire-Test-Response Characteristics: Provide through-penetration fire stop systems and fire-resistive joint systems that comply with specified requirements of tested systems.
- B. Fire stop System installation must meet requirements of ASTM E 814, UL 1479 or UL 2079 tested assemblies that provide a fire rating equal to that of construction being penetrated.
- C. Proposed fire stop materials and methods shall conform to applicable governing codes having local jurisdiction.



- D. Fire stop Systems do not reestablish the structural integrity of load bearing partitions/assemblies, or support live loads and traffic. Installer shall consult the structural engineer prior to penetrating any load bearing assembly.
- E. For those firestop applications that exist for which no qualified tested system is available through a manufacturer, an engineering judgment derived from similar qualified tested system designs or other tests will be submitted to local authorities having jurisdiction for their review and approval prior to installation. Engineering judgment documents must follow requirements set forth by the International Firestop Council.

1.07 SUBMITTALS

- A. Submit Product Data: Manufacturer's specifications and technical data for each material including the composition and limitations, documentation of qualified tested firestop systems to be used and manufacturer's installation instructions to comply with Section 01 30 00.
- B. Manufacturer's engineering judgment identification number and document details when no qualified tested system is available for an application. Engineering judgment must include both project name and contractor's name who will install firestop system as described in document.
- C. Submit material safety data sheets provided with product delivered to job-site.

1.08 INSTALLER QUALIFICATIONS

- A. Engage an experienced Installer who is certified, licensed, or otherwise qualified by the firestopping manufacturer as having been provided the necessary training to install manufacturer's products per specified requirements. A supplier's willingness to sell its firestopping products to the Contractor or to an Installer engaged by the Contractor does not in itself confer qualification on the buyer.
- B. Installation Responsibility: assign installation of through-penetration firestop systems and fire-resistive joint systems in Project to a single sole source firestop specialty contractor.
 - NOTE: THE REQUIREMENT FOR A SINGLE SOLE SOURCE FIRESTOP SPECIALTY CONTRACTOR IS A CONDITION OF THE BUILDING PERMIT FROM THE CITY OF PORTLAND AND IS NOT NEGOTIABLE. FIRESTOPPING CANNOT BE INSTALLED ON A TRADE-BY-TRADE BASIS.
- C. The work is to be installed by a contractor with at least one of the following qualifications:
 - FM 4991 Approved Contractor
 - UL Approved Contractor
 - Hilti Accredited Fire Stop Specialty Contractor

1.09 DELIVERY, STORAGE, AND HANDLING

- A. Deliver materials undamaged in manufacturer's clearly labeled, unopened containers, identified with brand, type, and UL label where applicable.
- B. Coordinate delivery of materials with scheduled installation date to allow minimum storage time at job-site.



- C. Store materials under cover and protect from weather and damage in compliance with manufacturer's requirements, including temperature restrictions.
- D. Comply with recommended procedures, precautions or remedies described in material safety data sheets as applicable.
- E. Do not use damaged or expired materials.

1.10 PROJECT CONDITIONS

- A. Do not use materials that contain flammable solvents.
- B. Schedule installation of firestopping after completion of penetrating item installation but prior to covering or concealing of openings.
- C. Verify existing conditions and substrates before starting work. Correct unsatisfactory conditions before proceeding.
- D. Weather conditions: Do not proceed with installation of firestop materials when temperatures exceed the manufacturer's recommended limitations for installation printed on product label and product data sheet.
- E. During installation, provide masking and drop cloths to prevent firestopping materials from contaminating any adjacent surfaces.

PART 2 - PRODUCTS

2.01 FIRESTOPPING - GENERAL

- A. Provide firestopping composed of components that are compatible with each other, the substrates forming openings, and the items, if any, penetrating the firestopping under conditions of service and application, as demonstrated by the firestopping manufacturer based on testing and field experience.
- B. Provide components for each firestopping system that are needed to install fill material. Use only components specified by the firestopping manufacturer and approved by the qualified testing agency for the designated fire-resistance-rated systems.
- C. Penetrations in Fire Resistance Rated Walls: Provide firestopping with ratings determined in accordance with UL 1479 or ASTM E 814.
 - 1. F-Rating: Not less than the fire-resistance rating of the wall construction being penetrated.
- D. Penetrations in Horizontal Assemblies: Provide firestopping with ratings determined in accordance with UL 1479 or ASTM E 814.
 - 1. F-Rating: Minimum of 1-hour rating, but not less than the fire-resistance rating of the floor construction being penetrated.
 - 2. T-Rating: when penetrant is located outside of a wall cavity, minimum of 1-hour rating, but not less than the fire-resistance rating of the floor construction being penetrated.
 - 3. W-Rating: Class 1 rating in accordance with water leakage test per UL 1479.

- E. Penetrations in Smoke Barriers: Provide firestopping with ratings determined in accordance with UL 1479 or ASTM E 814.
 - 1. L-Rating: Not exceeding 5.0 cfm/sq. ft. of penetration opening at both ambient and elevated temperatures.
- F. Mold Resistance: Provide penetration firestoppping with mold and mildew resistance rating of 0 as determined by ASTM G21.
- G. Firestopping Materials are either “cast-in-place” (integral with concrete placement) or “post installed.” Provide cast-in-place firestop devices prior to concrete placement.

2.02 ACCEPTABLE MANUFACTURERS

- A. Subject to compliance with through penetration firestop systems (XHEZ), joint systems (XHBN), and perimeter firestop systems (XHDG) listed in Volume 2 of the UL Fire Resistance Directory; provide products of the following manufacturers as identified below:
 - 1. Hilti, Inc., Tulsa, Oklahoma
800-879-8000
www.us.hilti.com
Chris Allington 508-509-8316
Chris.allington@hilti.com
 - 2. Substitution requests shall be considered in accordance with contract provisions.

2.03 MATERIALS

- A. Use only firestop products that have been UL 1479, ASTM E 814 or UL 2079 tested for specific fire-rated construction conditions conforming to construction assembly type, penetrating item type, annular space requirements, and fire-rating involved for each separate instance.
- B. Pre-installed firestop devices for use with noncombustible and combustible pipes (closed and open systems), conduit, and/or cable bundles penetrating concrete floors and/or gypsum walls, the following products are acceptable:
 - 1. Hilti Cast-In Place Firestop Device (CP 680-P)
 - a. Add Aerator Adaptor when used in conjunction with aerator system.
 - 2. Hilti Tub Box Kit (CP 681) for use with tub installations.
 - 3. Hilti Cast-In Place Firestop Device (CP 680-M) for use with noncombustible penetrants.
 - 4. Hilti Speed Sleeve (CP 653) for use with cable penetrations.
 - 5. Hilti Firestop Drop-In Device (CFS-DID) for use with noncombustible and combustible penetrants.
 - 6. Hilti Firestop Block (CFS-BL)
- C. Sealants, caulking materials, or foams for use with non-combustible items including steel pipe, copper pipe, rigid steel conduit and electrical metallic tubing (EMT), the following products are acceptable:
 - 1. Hilti Intumescent Firestop Sealant (FS-ONE)
 - 2. Hilti Self-leveling Firestop Sealant (CP 604)
 - 3. Hilti Fire Foam (CP 620)



4. Hilti Flexible Firestop Sealant (CP 606)
 5. Hilti Elastomeric Firestop Sealant (CP 601S)
- D. Sealants or caulking materials for use with sheet metal ducts, the following products are acceptable:
1. Hilti Elastomeric Firestop Sealant (CP 601S)
 2. Hilti Flexible Firestop Sealant (CP 606)
 3. Hilti Intumescent Firestop Sealant (FS-ONE)
- E. Sealants, caulking or spray materials for use with fire-rated construction joints and other gaps, the following products are acceptable:
1. Hilti Firestop Joint Spray (CFS-SP WB)
 2. Hilti Elastomeric Firestop Sealant (CP 601S)
 3. Hilti Flexible Firestop Sealant (CP 606)
 4. Hilti Self-leveling Firestop Sealant (CP 604)
- F. Pre-formed mineral wool designed to fit flutes of metal profile deck and gap between top of wall and metal profile deck; as a backer for spray material.
1. Hilti Speed Plugs (CP 777)
 2. Hilti Speed Strips (CP 767)
- G. Intumescent sealants, caulking materials for use with combustible items (penetrants consumed by high heat and flame) including insulated metal pipe, PVC jacketed, flexible cable or cable bundles and plastic pipe, the following products are acceptable:
1. Hilti Intumescent Firestop Sealant (FS-ONE)
- H. Foams, intumescent sealants, or caulking materials for use with flexible cable or cable bundles, the following products are acceptable:
1. Hilti Intumescent Firestop Sealant (FS-ONE)
 2. Hilti Fire Foam (CP 620)
 3. Hilti Elastomeric Firestop Sealant (CP 601S)
 4. Hilti Flexible Firestop Sealant (CP 606)
- I. Non-curing, re-penetrable intumescent putty or foam materials for use with flexible cable or cable bundles, the following products are acceptable:
1. Hilti Firestop Putty Stick (CP 618)
 2. Hilti Firestop Plug (CFS-PL)
- J. Wall opening protective materials for use with U.L. listed metallic and specified nonmetallic outlet boxes, the following products are acceptable:
1. Hilti Firestop Putty Pad (CP 617)
 2. Hilti Firestop Box Insert
- K. Firestop collar or wrap devices attached to assembly around combustible plastic pipe (closed and open piping systems), the following products are acceptable:
1. Hilti Firestop Collar (CP 643N)
 2. Hilti Firestop Collar (CP 644)



3. Hilti Wrap Strips (CP 648E/648S)
- L. Materials used for large openings and complex penetrations made to accommodate cable trays and bundles, multiple steel and copper pipes, electrical busways in raceways, the following products are acceptable:
 1. Hilti Firestop Mortar (CP 637)
 2. Hilti Firestop Block (CFS-BL)
 3. Hilti Fire Foam (CP 620)
 4. Hilti Firestop Board (CP 675T)
 - M. Non curing, re-penetrable materials used for large size/complex penetrations made to accommodate cable trays and bundles, multiple steel and copper pipes, electrical busways in raceways, the following products are acceptable:
 1. Hilti Firestop Block (CFS-BL)
 2. Hilti Firestop Board (CP 675T)
 - N. Sealants or caulking materials used for openings between structurally separate sections of wall and floors, the following products are acceptable:
 1. Hilti Firestop Joint Spray (CFS-SP WB)
 2. Hilti Elastomeric Firestop Sealant (CP 601S)
 3. Hilti Flexible Firestop Sealant (CP 606)
 4. Hilti Self-leveling Firestop Sealant (CP 604)
 - O. For blank openings made in fire-rated wall or floor assemblies, where future penetration of pipes, conduits, or cables is expected, the following products are acceptable:
 1. Hilti CFS-BL Firestop Block
 2. Hilti CFS-PL Firestop Plug
 - P. Provide a firestop system with a "F" Rating as determined by UL 1479 or ASTM E814 which is equal to the time rating of construction being penetrated.
 - Q. Provide a firestop system with an Assembly Rating as determined by UL 2079 which is equal to the time rating of construction joint assembly.

PART 3 - EXECUTION

3.01 PREPARATION

- A. Verification of Conditions: Examine areas and conditions under which work is to be performed and identify conditions detrimental to proper or timely completion.
 1. Verify penetrations are properly sized and in suitable condition for application of materials.
 2. Surfaces to which firestop materials will be applied shall be free of dirt, grease, oil, rust, laitance, release agents, water repellents, and any other substances that may affect proper adhesion.
 3. Provide masking and temporary covering to prevent soiling of adjacent surfaces by firestopping materials.
 4. Comply with manufacturer's recommendations for temperature and humidity conditions before, during and after installation of firestopping.



5. Do not proceed until unsatisfactory conditions have been corrected.

3.02 COORDINATION

- A. Coordinate construction of openings, penetrations and construction joints to ensure that the fire stop systems are installed according to specified requirements.
- B. Coordinate sizing of sleeves, openings, core-drilled holes, or cut openings to accommodate through-penetration fire stop systems. Coordinate construction and sizing of joints to ensure that fire-resistive joint systems are installed according to specified requirements.
- C. Coordinate fire stopping with other trades so that obstructions are not placed in the way prior to the installation of the fire stop systems.
- D. Do not cover up through-penetration fire stop and joint system installations that will become Concealed behind other construction until each installation has been examined by the building inspector.

3.03 INSTALLATION

- A. Regulatory Requirements: Install firestop materials in accordance with UL Fire Resistance Directory or Omega Point Laboratories Directory.
- B. Manufacturer's Instructions: Comply with manufacturer's instructions for installation of through-penetration and construction joint materials.
 - 1. Seal all holes or voids made by penetrations to ensure an air and water resistant seal.
 - 2. Consult with mechanical engineer, project manager, and damper manufacturer prior to installation of UL firestop systems that might hamper the performance of fire dampers as it pertains to duct work.
 - 3. Protect materials from damage on surfaces subjected to traffic.

3.04 FIELD QUALITY CONTROL

- A. Examine sealed penetration areas to ensure proper installation before concealing or enclosing areas.
- B. Keep areas of work accessible until inspection by applicable code authorities.
- C. Inspection of through-penetration firestopping shall be performed in accordance with ASTM E 2174, "Standard Practice for On-Site Inspection of Installed Fire Stops" or other recognized standard.
- D. Perform under this section patching and repairing of firestopping caused by cutting or penetrating of existing firestop systems already installed by other trades.
- E. Manufacturer's Field Services: During Installation, provide periodic destructive testing inspections to assure proper installation/application. After installation is complete, submit findings in writing indicating whether or not the installation of the tested system identified was installed correctly.

3.05 IDENTIFICATION & DOCUMENTATION

- A. The firestop contractor is to supply documentation for each single application addressed. This documentation is to identify each penetration and joint location on the entire project.
- A.1 The Documentation Form for through penetrations is to include:
1. A Sequential Location Number
 2. The Project Name
 3. Date of Installation
 4. Detailed description of the penetrations location
 5. Tested System or Engineered Judgment Number
 6. Type of assembly penetrated
 7. A detailed description of the size and type of penetrating item
 8. Size of opening
 9. Number of sides of assemblies addressed
 10. Hourly rating to be achieved
 11. Installers Name
- A.2 The Documentation Form for Construction Joints is to include:
1. A Sequential Location Number
 2. The Project Name
 3. Date of Installation
 4. Detailed description of the Construction Joints location
 5. Tested System or Engineered Judgment Number
 6. Type of Construction Joint
 7. The Width of the Joint
 8. The Lineal Footage of the Joint
 9. Number of sides addressed
 10. Hourly rating to be achieved
 11. Installers Name
- B. Copies of these documents are to be provided to the general contractor at the completion of the project.
- C. Identify through-penetration firestop systems with pressure-sensitive, self-adhesive, preprinted vinyl labels. Attach labels permanently to surfaces of penetrated construction on both sides of each firestop system installation where labels will be visible to anyone seeking to remove penetrating items or firestop systems. Include the following information on labels:
1. The words: "Warning -Through Penetration Firestop System-Do Not Disturb. Notify Building Management of Any Damage."
 2. Contractor's Name, address, and phone number.
 3. Through-Penetration firestop system designation of applicable testing and inspecting agency.
 4. Date of Installation.
 5. Through-Penetration firestop system manufacturer's name.
 6. Installer's Name.

3.06 ADJUSTING AND CLEANING



- A. Remove equipment, materials and debris, leaving area in undamaged, clean condition.
- B. Clean all surfaces adjacent to sealed holes and joints to be free of excess firestop materials and soiling as work progresses.

3.07 LABOR USE TO INSTALL FIRESTOP SYSTEMS

- A. To ensure complete harmony on the project site, the installation of each scope of work is to be performed jurisdictionally correct per existing trade agreements.

END OF SECTION