



Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 05/16/14

118 ON MUNJOY HILL – PORTLAND, MAINE

SECTION 08411 ALUMINUM STOREFRONT SYSTEMS

PART 1 GENERAL

1.01 SUMMARY

- A. Section Includes: Aluminum Swing Doors, including:
 - 1. YKK AP Series YES 45 TU Storefront System.
- B. Related Sections:
 - 1. Sealants: Refer to Division 7 Joint Treatment Section for sealant requirements.
 - 2. Glass and Glazing: Refer to Division 8 Glass and Glazing Section for glass and glazing requirements.

1.02 SYSTEM PERFORMANCE DESCRIPTION

- A. Performance Requirements: Provide aluminum storefront systems that comply with performance requirements indicated, as demonstrated by testing manufacturer's assemblies in accordance with test method indicated.
 - 1. Wind Loads: Completed storefront system shall withstand wind pressure loads normal to wall plane.
 - 2. Deflection: Maximum allowable deflection in any member when tested in accordance with ASTM E 330-90 with allowable stress in accordance with AA Specifications for Aluminum Structures.
 - a. Without Horizontals: $L/175$ or $3/4"$ (19.1mm) maximum. .
 - b. With Horizontals: $L/175$ or $L/240 + 1/4"$ (6.4mm) for spans greater than 13'-6" (4.1m) but less than 40'-0" (12.2m).
 - 3. Thermal Movement: Provide for thermal movement caused by 180 degrees F. (82.2 degrees C.) surface temperature, without causing buckling stresses on glass, joint seal failure, undue stress on structural elements, damaging loads on fasteners, reduction of performance, or detrimental effects.
 - 4. Air Infiltration: Completed storefront systems shall have 0.03 CFM/FT² (0.56 m³/h·m²) maximum allowable infiltration when tested in accordance with ASTM E 283-91 at differential static pressure of 6.24 PSF (299 Pa).
 - 5. Water Infiltration: No uncontrolled water on indoor face of any component when tested in accordance with ASTM E 331-93 at a static pressure of 12 PSF (718 Pa).
 - 6. Thermal Performance: When tested in accordance with AAMA 1503.1-88 and ASTM C 236-89:
 - a. Condensation Resistance Factor (CRF): A minimum of 63.
 - b. Thermal Transmittance U Value: 0.46 BTU/HR/FT²/°F or less.
- Note: The CRF for the glazed system as a whole will be affected by the characteristics of the glass specified.

1.03 SUBMITTALS

- A. General: Prepare, review, approve, and submit specified submittals in accordance with "Conditions of the Contract" and Division 1 Submittals Sections. Product data, shop drawings, samples, and similar submittals are defined in "Conditions of the Contract."
- B. Product Data: Submit product data for each type storefront series specified.
- C. Shop Drawings: Submit shop drawings showing layout, profiles, and product components, including anchorage, accessories, finish colors and textures.
- D. Samples: Submit verification samples for colors on actual aluminum substrates indicating full color range expected in installed system.
- E. Quality Assurance / Control Submittals:
 - 1. Test Reports: Submit certified test reports showing compliance with specified performance characteristics and physical properties.
 - 2. Installer Qualification Data: Submit installer qualification data.
- F. Closeout Submittals:
 - 1. Warranty: Submit warranty documents specified herein.
 - 2. Project Record Documents: Submit project record documents for installed materials in accordance with Division 1 Project Closeout (Project Record Documents) Section.

1.04 QUALITY ASSURANCE

- A. Qualifications:
 - 1. Installer Qualifications: Installer experienced (as determined by contractor) to perform work of this section who has specialized in the installation of work similar to that required for this project. If requested by Owner, submit reference list of completed projects.
- B. Pre-Installation Meetings: Conduct pre-installation meeting to verify project requirements, substrate conditions, manufacturer's installation instructions, and manufacturer's warranty requirements.



Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 05/16/14

118 ON MUNJOY HILL – PORTLAND, MAINE

1.05 PROJECT CONDITIONS / SITE CONDITIONS

- A. Field Measurements: Verify actual measurements/openings by field measurements before fabrication; show recorded measurements on shop drawings. Coordinate field measurements, fabrication schedule with construction progress to avoid construction delays.

1.06 WARRANTY

- A. Project Warranty: Refer to "Conditions of the Contract" for project warranty provisions.
- B. Manufacturer's Warranty: Submit, for Owner's acceptance, manufacturer's standard warranty document executed by authorized company official. Manufacturer's warranty is in addition to, and not a limitation of, other rights Owner may have under the Contract Documents.
 - 1. Beneficiary: Issue warranty in the legal name of the project Owner.
 - 2. Warranty Period: Two years commencing on Date of Substantial Completion.
 - 3. Warranty Acceptance: Owner is sole authority who will determine acceptability of manufacturer's warranty documents.

PART 2 PRODUCTS

2.01 MANUFACTURERS (Acceptable Manufacturers/Products)

- A. Acceptable Manufacturers: YKK AP America Inc.
7680 The Bluffs, Suite 100
Austell, GA 30168
Telephone: (678) 838-6000; Fax: (678) 838-6001
 - 1. Storefront System: YKK AP YES 45 TU Storefront System.
- B. Storefront Framing System:
 - 1. Description: Center set, exterior flush glazed; jambs and vertical mullions continuous; head, sill, intermediate horizontal attached by screw spline joinery or shear block attachment.
 - 2. Components: Manufacturer's standard extruded aluminum mullions, 90 degree corner posts, entrance door framing, and indicated shapes.
 - 3. Thermal Barrier: Provide continuous thermal barrier by means of a poured and debridged pocket consisting of a two-part, chemically curing high density polyurethane which is bonded to the aluminum by YKK ThermoBond Plus™. Systems employing non-structural thermal barriers are not acceptable.

2.02 MATERIALS

- A. Extrusions: ASTM B 221 (ASTM B 221M), 6063-T5 Aluminum Alloy.
- B. Aluminum Sheet:
 - 1. Painted Finish: ASTM B 209 (ASTM B 209M), 3003-H14 Aluminum Alloy, 0.080" (1.95 mm) minimum thickness.

2.03 ACCESSORIES

- A. Manufacturer's Standard Accessories:
 - 1. Fasteners: Zinc plated steel concealed fasteners; Hardened aluminum alloys or AISI 300 series stainless steel exposed fasteners, countersunk, finish to match aluminum color.
 - 2. Sealant: Non-skinning type, AAMA 803.3
 - 3. Glazing: Setting blocks, edge blocks, and spacers in accordance with ASTM C 864, shore durometer hardness as recommended by manufacturer; Glazing gaskets in accordance with ASTM C 864.

2.04 RELATED MATERIALS (Specified In Other Sections)

- A. Glass: Refer to Division 8 Glass and Glazing Section for glass materials.

2.05 FABRICATION

- A. Shop Assembly: Fabricate and assemble units with joints only at intersection of aluminum members with uniform hairline joints; rigidly secure, and sealed in accordance with manufacturer's recommendations.
 - 1. Hardware: Drill and cut to template for hardware. Reinforce frames and door stiles to receive hardware in accordance with manufacturer's recommendations.
 - 2. Welding: Conceal welds on aluminum members in accordance with AWS recommendations or methods recommended by manufacturer. Members showing welding bloom or discoloration on finish or material distortion will be rejected.



Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 05/16/14

118 ON MUNJOY HILL – PORTLAND, MAINE

B. Fabrication Tolerances:

1. Material Cuts: Square to 1/32 inch (0.8 mm) off square, maximum, over largest dimension; proportionate amount of 1/32 inch (0.8 mm) on other two dimensions.
2. Maximum Offset: 1/64 inch (0.4 mm) in alignment between two consecutive members in line, end to end.
3. Maximum Offset: 1/64 inch (0.4 mm) between framing members at glazing pocket corners.
4. Joints (Between adjacent members in same assembly): Hairline and square to adjacent member.
5. Variation (In squaring diagonals for doors and fabricated assemblies): 1/16 inch (1.6 mm).
6. Flatness (For doors and fabricated assemblies): +/- 1/16 inch (1.6 mm) off neutral plane.

2.06 FINISHES AND COLORS

A. High Performance Organic Coating Finish:

1. Type Factory applied two-coat 70% Kynar resin by Auto Chem or 70% Hylar resin by Ausimont, fluoropolymer based coating system, Polyvinylidene Fluoride (PVF-2), applied in accordance with YKK AP procedures and meeting AAMA 2605 specifications.
2. Colors: Selected by Architect from the following:
 - a. Standard coating color charts.

B. Finishes Testing:

1. Apply 0.5% solution NaOH, sodium hydroxide, to small area of finished sample area; leave in place for sixty minutes; lightly wipe off NaOH; Do not clean area further.
2. Submit samples with test area noted on each sample.

PART 3 EXECUTION

3.01 MANUFACTURER'S INSTRUCTIONS / RECOMMENDATIONS

- A. Compliance: Comply with manufacturer's product data, including product technical bulletins, product catalog installation instructions, and product carton instructions.

3.02 EXAMINATION

- A. Site Verification of Conditions: Verify conditions (which have been previously installed under other sections) are acceptable for product installation in accordance with manufacturer's instructions.

3.03 PREPARATION

- A. Adjacent Surfaces Protection: Protect adjacent work areas and finish surfaces from damage during product installation.
 1. Aluminum Surface Protection: Protect aluminum surfaces from contact with lime, mortar, cement, acids, and other harmful contaminants.

3.04 INSTALLATION

- A. General: Install manufacturer's system in accordance with shop drawings, and within specified tolerances.
 1. Protect aluminum members in contact with masonry, steel, concrete, or dissimilar materials using nylon pads or bituminous coating.
 2. Shim and brace aluminum system before anchoring to structure.
 3. Provide sill flashing at exterior storefront systems. Extend extruded flashing continuous with splice joints; set in continuous beads of sealant.
 4. Verify storefront system allows water entering system to be collected in gutters and wept to exterior. Verify metal joints are sealed in accordance with manufacturers installation instructions.
 5. Locate expansion mullions where indicated on reviewed shop drawings.
 6. Seal metal to metal storefront system joints using sealant recommended by system manufacturer.

3.05 FIELD QUALITY CONTROL

- A. Manufacturer's Field Services: Upon Owner's request, provide manufacturer's field service consisting of product use recommendations and periodic site visit for inspection of product installation in accordance with manufacturer's instructions.
- B. Field Test: Conduct field test to determine watertightness of storefront system. Conduct test in accordance with AAMA 501.3-94 at locations selected by Architect.
 1. Perform minimum of one test. Perform test in Architect's presence.



3.06 ADJUSTING AND CLEANING

- A. Adjusting: Adjust swing doors for operation in accordance with manufacturer's recommendations.
- B. Cleaning: The General Contractor shall clean installed products in accordance with manufacturer's instructions prior to owner's acceptance, and remove construction debris from project site. Legally dispose of debris.
- C. Protection: The General Contractor shall protect the installed product's finish surfaces from damage during construction.

END OF SECTION