



SECTION 16190

SUPPORTING DEVICES

PART 1 - GENERAL

1.1 SECTION INCLUDES

- A. Conduit, cable and equipment supports.
- B. Fastening hardware.

1.2 QUALITY ASSURANCE

- A. Support systems shall be adequate for weight of equipment and conduit, including wiring, which they carry.

PART 2 - PRODUCTS

2.1 MATERIAL

- A. Support Channel: Galvanized or painted steel.
- B. Hardware: Corrosion resistant.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install products in accordance with manufacturer's instructions.
- B. Fasten hanger rods, conduit clamps, and outlet and junction boxes to building structure using expansion anchors and/or beam clamps.
- C. Anchors and Fasteners:
  - 1. Concrete Structural Elements: Use expansion anchors.
  - 2. Steel Structural Elements: Use beam clamps.
  - 3. Concrete Surfaces: Use self-drilling anchors and expansion anchors.
  - 4. Hollow Masonry, Plaster, and Gypsum Board Partitions: Use toggle bolts and hollow wall fasteners.
  - 5. Solid Masonry Walls: Use expansion anchors.
  - 6. Sheet Metal: Use sheet metal screws.
  - 7. Wood Elements: Use wood screws.

## 118 ON MUNJOY HILL – PORTLAND, MAINE



Reviewed for Code Compliance

Inspection Division

Approved with Conditions

Date: 05/16/14

- D. Do not fasten supports to piping, ductwork, mechanical equipment, or conduit.
- E. Do not use powder-actuated anchors.
- F. Do not drill structural steel members.
- G. Fabricate supports or trapeze hangers from structural steel or steel channel, rigidly welded or bolted to present a neat appearance. Use hexagon head bolts with spring lock washers under all nuts.
- H. Bridge studs to and bottom with horizontal members to support flush-mounted loadcenters in new stud walls.

END OF SECTION