CITY OF PORTLAND ELECTRONIC STAMP:

1 EAST EXTERIOR ELEVATION
SCALE: 1/4" = 1'-0"

2 WEST EXTERIOR ELEVATION
SCALE: 1/4" = 1'-0"

WINDOW SCHEDULE				
Mark	Type	Nominal W x...	Sill/Header Value	Type
A	ETR	2'x4'	48.00"	
B	ETR	2'-9"x3'-3 1/2"	43.75"	
C	New	2'x4'	42.00"	TBD
D	New	4'x5'	18.00"	TBD
E1	New	2'-3"x5'	36.25"	TBD
E2	New	2'-3"x5'	36.25"	TBD
E3	New	2'-3"x5'	36.25"	TBD
F	ETR	2'-7 1/2"x3'-6 1/2"	30.25"	
G	ETR	7'-9"x4'-9"	24.00"	
H	New	2'-8"x4'	42.00"	TBD
I	ETR	2'-9"x5'-7"	23.50"	
J	ETR	6'-7"x5'-7"	23.50"	

1. Verify Size of all existing windows and rough openings in field

4 WINDOW SCHEDULE
SCALE: 1' = 1'-0"

DOOR AND FRAME SCHEDULE			
ID	New or Existing	Leaf Dimensions	Notes
1	New	2'-10"x6'-8"	TBD, Egress Door
2	ETR	2'-3 1/2"x6'-9 1/2"	
3	ETR	2'-8"x6'-9 1/2"	
4	New	1'-6"x6'-8"	TBD
5	New	3'x6'-8"	TBD
6	New	2'-6"x6'-8"	TBD
7	New	2'-10"x6'-8"	TBD
8	New	2'-6"x6'-8"	TBD
9	New	2'-6"x6'-8"	TBD
10	New	2'-10"x6'-8"	TBD
11	New	2'x6'-8"	TBD

1. Verify Size of all existing door and rough openings in field

5 DOOR SCHEDULE
SCALE: 1' = 1'-0"

3 SOUTH ELEVATION
SCALE: 1/4" = 1'-0"

CALEB JOHNSON
ARCHITECTS + BUILDER
265 MAIN STREET, SUITE 201 BIDDEFORD, ME 04005
T: 207.283.8777 F: 207.283.8778
C.J.A.B.A.

Reviewed for Code Compliance
Inspections Division
Date: 03/05/15

PROJECT STATUS:
PERMIT SET
STUDIO MANAGER:
MICHAEL CHESNUTT, RA
PROJECT ARCHITECT:
CALEB JOHNSON, AIA

SUBMISSIONS:
2015-01-14 PERMIT SET

CONSULTANTS:

DRAFTSPERSON:
PATRICK BOOTHE, AIA
DATE OF ISSUE:
1/14/15
PROJECT STATUS:
PERMIT SET

PERMIT SET

JOHNSON-WINTER INTERIOR RENOVATION
DAVID JOHNSON & DHARMASURI WINTER
26 MONUMENT ST PORTLAND ME 04041 USA

LICENSED ARCHITECT
CALEB A. JOHNSON
NO. 2919
STATE OF MAINE

ELEVATIONS & SCHEDULES
A-2.1

/Volumes/Network Files/CJAB/PROJECTS/1 CURRENT PROJECTS/JOHNSON WINTER/1 DESIGN/DRAWINGS/JOHNSON AND WINTER_Current.pln