PLAN NORTH

NOTES:
1. PROVIDE SIMPSON RAFTER HANGERS AT ALL RAFTER ENDS, TYP.
2. WINDOW HEADERS SHALL BE (2)-2x8's, U.N.O.
3. PROVIDE (3)-2x4 STUDS AT ALL CORNERS, COLUMNS AND HOLD-DOWN LOCATIONS U.N.O.
4. SEE SHEAR WALL ELEVATIONS ON SHEET S401 FOR SHEAR WALL LOCATIONS AND FASTENING INFORMATION.

PLAN LEGEND
- BEARING WALL
- SHEAR WALL
- BEAM
- COLUMN FROM ABOVE
- COLUMN BELOW
- COLUMN ABOVE AND BELOW
- HOLD-DOWN

FOURTH FLOOR & ROOF FRAMING PLAN

SCALE: 1/4"=1'-0" | 1

NOTES:
1. PROVIDE SIMPSON JOIST HANGERS AT ALL JOIST ENDS, TYP.
2. WINDOW HEADERS SHALL BE (2)-2x8's, U.N.O.
3. PROVIDE (3)-2x4 STUDS AT ALL CORNERS, COLUMNS AND HOLD-DOWN LOCATIONS U.N.O.
4. SEE SHEAR WALL ELEVATIONS ON SHEET S401 FOR SHEAR WALL LOCATIONS AND FASTENING INFORMATION.

PLAN LEGEND
- BEARING WALL
- SHEAR WALL
- BEAM
- COLUMN FROM ABOVE
- COLUMN BELOW
- COLUMN ABOVE AND BELOW
- HOLD-DOWN

UPPER DECK FRAMING PLAN

SCALE: 1/4"=1'-0" | 2

CASCO BAY ENGINEERING
424 Fore Street
Portland, ME 04101
Phone 207.842.2800
Fax 207.842.2828
www.cascobayengineering.com

CLIENT:
CORNERSTONE BUILDING & RESTORATION
44 COYLE STREET
PORTLAND, ME 0410

STATE OF MAINE ANTHONY DUMAIS No. 12851 LICENSED PROFESSIONAL ENGINEER
Anthony Dumais

MONUMENT STREET
PORTLAND MAINE
NEW RESIDENCE

ISSUED

No.	DESCRIPTION	DR. BY	CKD. BY	DATE
A	ISSUED FOR PERMIT	TD	TD	10-20-14
0	ISSUED FOR CONSTRUCTION	TD	TD	1-6-15

SHEET TITLE:
FOURTH FLOOR/ ROOF & UPPER DECK FRAMING PLANS

DESIGNED:	TD
DRAWN:	TD
DATE:	10-2-14
PROJECT NUMBER:	14-121

S103

PRINTED: Jan 06, 2015
Inspection Division Date: 01/13/15