PLAN NORTH

NOTES:
1. PROVIDE SIMPSON JOIST HANGERS AT ALL JOIST ENDS, TYP.
2. WINDOW HEADERS SHALL BE (2)-2x8's, U.N.O.
3. PROVIDE (3)-2x4 STUDS AT ALL CORNERS, COLUMNS AND HOLD-DOWN LOCATIONS U.N.O.
4. SEE SHEAR WALL ELEVATIONS ON SHEET S401 FOR SHEAR WALL LOCATIONS AND FASTENING INFORMATION.

PLAN LEGEND
- BEARING WALL
- SHEAR WALL
- BEAM
- COLUMN FROM ABOVE
- COLUMN BELOW
- COLUMN ABOVE AND BELOW
- HOLD-DOWN

SECOND FLOOR FRAMING PLAN

SCALE: 1/4"=1'-0" | 1

NOTES:
1. PROVIDE SIMPSON JOIST HANGERS AT ALL JOIST ENDS, TYP.
2. WINDOW HEADERS SHALL BE (2)-2x8's, U.N.O.
3. PROVIDE (3)-2x4 STUDS AT ALL CORNERS, COLUMNS AND HOLD-DOWN LOCATIONS U.N.O.
4. SEE SHEAR WALL ELEVATIONS ON SHEET S401 FOR SHEAR WALL LOCATIONS AND FASTENING INFORMATION.

PLAN LEGEND
- BEARING WALL
- SHEAR WALL
- BEAM
- COLUMN FROM ABOVE
- COLUMN BELOW
- COLUMN ABOVE AND BELOW
- HOLD-DOWN

THIRD FLOOR FRAMING PLAN

SCALE: 1/4"=1'-0" | 2

PRINTED: Jan 06, 2015

CASCO BAY ENGINEERING
424 Fore Street
Portland, ME 04101
Phone 207.842.2800
Fax 207.842.2828
www.cascobayengineering.com

CLIENT:
CORNERSTONE BUILDING & RESTORATION
44 COYLE STREET
PORTLAND, ME 0410

STATE OF MAINE
ANTHONY DUMAIS
No. 12851
LICENSED
PROFESSIONAL ENGINEER
Anthony Dumais

MONUMENT STREET
PORTLAND MAINE
NEW RESIDENCE

ISSUED

No.	DESCRIPTION	DR. BY	CKD. BY	DATE
A	ISSUED FOR PERMIT	TD	TD	10-20-14
0	ISSUED FOR CONSTRUCTION	TD	TD	1-6-15

SHEET TITLE:
SECOND FLOOR & THIRD FLOOR FRAMING PLANS

DESIGNED:	TD
DRAWN:	TD
DATE:	10-2-14
PROJECT NUMBER:	14-121

S102