Reviewed for Code Compliance
Inspections Division
Date: 12/06/16

WINDOW SCHEDULE

Unit	Style	MFGR	Description	Width	Height	Notes	above subfloor	Temp.	Egress	U-factor	SHGC	VLT
A	Casement	TBD	LH	2'-8 1/2"	5'-6"		V.I.F.	NO	YES	U≤0.30	TBD	
B	Fixed	TBD	Fixed	1'-4 1/2"	5'-6"		V.I.F.	NO	NO	U≤0.30	TBD	
C	Casement	TBD	LH	3'-3 1/4"	5'-6"		V.I.F.	NO	YES	U≤0.30	TBD	
D	Mulled Casement	TBD	3-Unit, Factory Mull, LH-Fixed-RH	6'-6"	3'-3 1/4"		V.I.F.	NO	NO	U≤0.30	TBD	
E	Casement	TBD	LH	2'-8 1/2"	5'-4 1/2"		V.I.F.	NO	YES	U≤0.30	TBD	
E1	Casement	TBD	RH	2'-8 1/2"	5'-4 1/2"		V.I.F.	YES	NO	U≤0.30	TBD	
F	Casement	TBD	LH	3'-3 1/4"	5'-4 1/2"		V.I.F.	NO	YES	U≤0.30	TBD	
G	Fixed	TBD	Fixed	1'-4 1/2"	5'-4 1/2"		V.I.F.	NO	NO	U≤0.30	TBD	
H1	Casement	TBD	LH - MC1 7512	2'-5 1/2"	3'-11 1/4"		Match Existing HH	NO	YES	U≤0.30	TBD	
H2	Casement	TBD	RH - MC1 7512	2'-5 1/2"	3'-11 1/4"		Match Existing HH	NO	YES	U≤0.30	TBD	
I	Awning	TBD	AW1 0506	1'-7 11/16"	1'-11 5/8"		Match Existing HH	NO	NO	U≤0.30	TBD	
J	Mulled Casement	TBD	3-Unit, Factory Mull, LH-Fixed-RH MC1 0815	8'-6 1/2"	4'-11 1/16"		Match Existing HH	NO	YES	U≤0.30	TBD	
K	Skylight	Velux	VS-M06 Venting skylight	2'-6 9/16"	3'-10 1/4"	Integrated manual blackout shade, color tbd						
L	Casement	TBD	LH	2'-9 3/4"	5'-3 1/4"		V.I.F.	NO	YES	U≤0.30	TBD	
M	Skylight	Velux	VS-M02 Venting skylight	2'-6 9/16"	2'-6 1/2"	Integrated manual blackout shade, color tbd						
N	Awning	TBD		2'-8 1/2"	3'-0 1/2"		Match Existing HH	NO	NO	U≤0.30	TBD	

Notes:
1. All windows to be replaced except at existing rear addition
2. Combo unit mulling location: factory
3. Glazing: Triple-glazed, Low-E/Clear/Low-E, Argon Gas
4. Performance: U-value </= 0.30 BTU/(hr.ft2.F) SHGC </=
5. Hardware: TBD
6. Insect screen: Gray
7. Exterior: Aluminum, Color TBD
8. Interior: Natural finish
9. All window sizes to be confirmed by contractor in field prior to order.

DOOR SCHEDULE

EXTERIOR DOORS				Door unit size				Glazing			
Unit	Style	MFGR	Description	Width	Height	Notes	Swing	U-factor	SHGC		VLT
101a	Entry	TBD	Sidelights + Transom	5'-0"	6'-8"		LHIS				
104a	Entry	TBD		2'-8"	6'-8"		RHIS				
INTERIOR DOORS				Door slab size				Glazing			
Unit	Style	MFGR	Description	Width	Height	Notes	Swing	U-factor	SHGC		VLT

Ext. Door Notes:
1. Combo unit mulling location: factory
2. Glazing: Triple-insulated, Low-E/Clear/Low-E, Argon Gas
3. Performance: U-value </= 0.30 BTU/(hr.ft2.F) SHGC </=
4. Hardware: TBD
5. Insect screen: Gray
6. Exterior: TBD
7. Interior: TBD
8. All door sizes to be confirmed by contractor in field prior to order.

Int. Door Notes:
1. Hardware: TBD
2. Panel type, TBD
3. Slab material, See Schedule
4. All door sizes to be confirmed by contractor in field prior to order.

KEY

NOTE:
WINDOW/DOOR OPERATION IS INDICATED BY DASHED LINE, POINT OF ARROW INDICATES PANEL SIDE WITH HINGES

PLUMBING SCHEDULE

ELECTRICAL SCHEDULE

FINISH SCHEDULE

© COPYRIGHT 2016 MICHAEL MAINES RESIDENTIAL DESIGN, LLC

MICHAEL MAINES
RESIDENTIAL DESIGN
336 N PALERMO RD
PALERMO, ME 04354
207-318-6224
mike@michaelmaines.com

RENOVATIONS TO THE
SWEET-HOLDEN RESIDENCE
37 ST. LAWRENCE STREET - PORTLAND, MAINE 04101

PERMIT SET
ISSUED FOR CONSTRUCTION

DATE	October 6, 2016
REV	November 4, 2016
REV	

SHEET
G601