Date: 12/11/13
Approved with Conditions

NOTE:
ALL (3) BOILERS TO BE PENSOTTI PGI 18% NATURAL GAS BOILERS. BOILERS DIRECT VENT THROUGH WALL AND SUPPLY HEAT AND DHW.

NOTES:
TYPICAL HEAT VIA UNDERFLOOR RADIANT HEAT TUBING. ALUMINUM "T" CHANNEL @ UNDERSIDE OF SUBFLOOR. 1/2" O2 BARRIER PEX PEX IN RADIANT HEAT RUNS.

GAS IRON PIPE SIZING BASED ON 60,000 BTU BOILER, 65,000 BTU STOVE, 35,000 BTU DRYER.

1	BASEMENT MECHANICAL AND GAS PLAN
	SCALE = 1/4" = 1'-0"

2	FIRST FLOOR MECHANICAL AND GAS PLAN
	SCALE = 1/4" = 1'-0"

3	SECOND FLOOR MECHANICAL AND GAS PLAN
	SCALE = 1/4" = 1'-0"

4	THIRD FLOOR MECHANICAL AND GAS PLAN
	SCALE = 1/4" = 1'-0"

MECHANICAL DESIGN/BUILD BY JIM MICHAUD, JIM'S PLUMBING & HEATING, 207-854-8068

DRAFTED BY LACHMAN ARCHITECTS AND PLANNERS

ALTERATIONS TO 52 MONUMENT STREET PORTLAND, MAINE

TITLE:
MECHANICAL FLOOR PLANS

DATE:
ORIGINAL: 11/05/13
REVISION 1: 12/10/13
REVISION 2:
REVISION 3:

ISSUED FOR:
CONSTRUCTION

DRAWING NO:
M1