Date: 08/14/14
Approved with Conditions

MATERIAL SCHEDULE

	TYPE/ LOCATION	FINISH	MANUFACTURER	SPECIFICATION	SIZE	NOTES
WD-1	WOOD FLOOR	CLEAR	-		PLANK	
CT-1	CERAMIC FLOOR TILE					
CT-2	CERAMIC FLOOR TILE					
CWT-1	CERAMIC WALL TILE					
CPT-1	CARPET					
WDB-1	WOOD BASE	PAINT		-		PREMIUM PINE W/ LACQUER SEALED KNOTS
PT-1	PAINT		-	--		
PT-2	PAINT					
PT-3	PAINT					
PT-4	PAINT					

WINDOW SCHEDULE

	LOCATION	STATUS	WIDTH x HEIGHT	NOTES
101/A	ENTRY STAIRS 101	NEW	2'6"x4'6"	MARVIN INTEGRITY WOOD/ULTREX DBH WINDOWS, CLAD INTERIOR, WOOD INTERIOR. MARVIN INTEGRITY FOR REPLACEMENT AND NEW WINDOWS TEMPERED WHERE REQUIRED AS PER CODE
102/A	BED ROOM 102	NEW	2'6"x7'0"	
102/B	BED ROOM 102	NEW	2'6"x7'0"	
102/C	BED ROOM 102	NEW	2'6"x7'0"	
103/A	DINING ROOM 103	NEW	2'6"x7'0"	NOTE: WINDOWS 101A, 102A, 102B, 102C, 103A, AND 201A ARE LIKELY REQ'D TO BE TEMPERED PER CODE. CONTRACTOR TO CONFIRM CODE REQ'D TEMPERED WDOS WITH WDO MANUFACTURER BEFORE ORDERING
103/B	DINING ROOM 103	NEW	2'6"x4'6"	
103/C	DINING ROOM 103	NEW	2'6"x4'6"	
104/A	BATHROOM 104	NEW	2'6"x4'6"	NOTE: WDO 304A IS AN EXISTING WDO. NOT PREVIOUSLY SHOWN ON DEMO PLANS. SEE D1 FOR UPDATE.
105/A	KITCHEN 105	NEW	1'2"x4'6"	
107/A	LIVING ROOM 107	NEW	2'6"x4'6"	
107/B	LIVING ROOM 107	NEW	3'0"x5'0"	
107/C	LIVING ROOM 107	NEW	3'0"x5'0"	
107/D	LIVING ROOM 107	NEW	3'0"x5'0"	
107/E	LIVING ROOM 107	NEW	2'6"x4'6"	
201/A	ENTRY STAIRS 201	NEW	2'6"x4'6"	
201/B	ENTRY STAIRS 201	NEW	2'6"x4'6"	
202/A	BEDROOM 202	NEW	2'6"x4'6" ESCAPE	
202/B	BEDROOM 202	NEW	2'6"x4'6"	
202/C	BEDROOM 202	NEW	2'6"x4'6"	
203/A	BEDROOM 203	NEW	2'6"x4'6" ESCAPE	
203/B	BEDROOM 203	NEW	2'6"x4'6"	
203/C	BEDROOM 203	NEW	2'6"x4'6"	
204/A	BATHROOM 204	NEW	2'6"x4'6"	
205/A	KITCHEN 205	NEW	1'2"x4'6"	
206/A	DINING 206	NEW	2'6"x5'6"	
207/A	LIVING ROOM 207	NEW	2'6"x4'6"	
207/B	LIVING ROOM 207	NEW	3'0"x5'0"	
207/C	LIVING ROOM 207	NEW	3'0"x5'0"	
207/D	LIVING ROOM 207	NEW	2'6"x4'6"	
301/A	STAIRWAY 301	NEW	(2) 46"x46" SKYLIGHTS	(2) VELUX 46" X 46" MULLED SKYLIGHTS
302/A	BEDROOM 302	NEW	2'6"x4'6" ESCAPE	
302/B	BEDROOM 302	NEW	1'10"x4'4"	
302/C	BEDROOM 302	NEW	4'0"x6'0"	
302/D	BEDROOM 302	NEW	1'10"x4'4"	
303/A	BEDROOM 303	NEW	2'6"x4'6" ESCAPE	
303/B	BEDROOM 303	NEW	1'10"x4'4"	
303/C	BEDROOM 303	NEW	4'0"x6'0"	
303/D	BEDROOM 303	NEW	1'10"x4'4"	
304/A	BATHROOM 304	NEW	2'6"x4'6"	
305/A	KITCHEN 305	NEW	1'2"x4'6"	
307/A	LIVING ROOM 307	NEW	2'6"x4'6"	
307/B	LIVING ROOM 307	NEW	3'0"x5'0"	
307/C	LIVING ROOM 307	NEW	3'0"x5'0"	
307/D	LIVING ROOM 307	NEW	2'6"x4'6"	

FINISH LEGEND

		WALLS						
LOCATION	FLOOR	NORTH	EAST	SOUTH	WEST	CEILING	BASE	NOTES
ENTRY 100	WOOD	GWB	GWB	GWB	GWB	GWB	WOOD	
ENTRY STAIRS 101	CARPET	GWB	GWB	GWB	GWB	GWB	WOOD	
BED ROOM 102	EXISTING WOOD	GWB	GWB	GWB	GWB	GWB	WOOD	
DINING ROOM 103	EXISTING WOOD	GWB	GWB	GWB	GWB	GWB	WOOD	
BATHROOM 104	TILE	GWB	GWB	GWB	GWB	GWB	TILE	
KITCHEN 105	WOOD	GWB	GWB	GWB	GWB	GWB	WOOD	
CLOSET/MUDROOM 106	WOOD	GWB	GWB	GWB	GWB	GWB	WOOD	
LIVING ROOM 107	WOOD	GWB	GWB	GWB	GWB	GWB	WOOD	
DECK 108	COMPOSITE							
ENTRY 200	WOOD	GWB	GWB	GWB	GWB	GWB	WOOD	
ENTRY STAIRS 201	CARPET	GWB	GWB	GWB	GWB	GWB	WOOD	
BEDROOM 202	EXISTING WOOD	GWB	GWB	GWB	GWB	GWB	WOOD	
BEDROOM/OFFICE 203	EXISTING WOOD	GWB	GWB	GWB	GWB	GWB	WOOD	
BATHROOM 204	TILE	GWB	GWB	GWB	GWB	GWB	TILE	
KITCHEN 205	WOOD	GWB	GWB	GWB	GWB	GWB	WOOD	
DINING ROOM 206	WOOD	GWB	GWB	GWB	GWB	GWB	WOOD	
LIVING ROOM 207	WOOD	GWB	GWB	GWB	GWB	GWB	WOOD	
DECK 208	COMPOSITE							
ENTRY 300	WOOD	GWB	GWB	GWB	GWB	GWB	WOOD	
ENTRY STAIRS 301	CARPET	GWB	GWB	GWB	GWB	GWB	WOOD	
BEDROOM 302	WOOD	GWB	GWB	GWB	GWB	GWB	WOOD	
BEDROOM 303	WOOD	GWB	GWB	GWB	GWB	GWB	WOOD	
BATHROOM 304	TILE	GWB	GWB	GWB	GWB	GWB	TILE	
KITCHEN 305	WOOD	GWB	GWB	GWB	GWB	GWB	WOOD	
DINING ROOM 306	WOOD	GWB	GWB	GWB	GWB	GWB	WOOD	
LIVING ROOM 307	WOOD	GWB	GWB	GWB	GWB	GWB	WOOD	
DECK 308	COMPOSITE							

DOOR SCHEDULE

								FRAME		HARD-	
	LOCATION	WIDTH x HEIGHT	THICKNESS	MATERIAL	TYPE	GLAZING	RATING	MATERIAL	THRESHOLD	WARE GROUP	SUGGESTED FUNCTION
101/1	ENTRY	(2) 2'-2"X6'-8"	1 3/8"	WOOD	A	FULL		WOOD/PT-2	4	1	KEYED
101/2	BASEMENT	3'0"X6'-8"	1 3/8"	STEEL	B		1 HR	WOOD/PT-2	1	1	PASSAGE, SELF CLOSING
101/3	ENTRY	3'-0"X6'-8"	1 3/8"	STEEL	B		1 HR	WOOD/PT-2	3	1	KEYED, SELF CLOSING
102/1	BEDROOM	(2) 4'-0"X6'-8"	1 3/8"	WOOD	A			WOOD/PT-2	1	1	PRIVACY
104/1	BATHROOM 104	2'-8X6'-8"	1 3/8"	WOOD	A			WOOD/PT-2	2	1	PRIVACY
106/1	CLOSET/MUDROOM	2'-6"X6'-8"	1 3/8"	WOOD	A	FULL		WOOD/PT-2	4	1	KEYED
201/1	ENTRY STAIRS 201	3'-0"X6'-8"	1 3/8"	STEEL	B		1 HR	WOOD/PT-2		1	KEYED, SELF CLOSING
202/1	BEDROOM 202	2'-6"X6'-8"	1 3/8"	WOOD	A			WOOD/PT-2		1	PRIVACY
202/2	BEDROOM 202	(2) 2'-0"X6'-8"	1 3/8"	WOOD	A			WOOD/PT-2		1	PASSAGE
203/1	BEDROOM/OFFICE 203	2'-6"X6'-8"	1 3/8"	WOOD	A			WOOD/PT-2		1	PRIVACY
203/2	BEDROOM/OFFICE 203	(2) 2'-0"X6'-8"	1 3/8"	WOOD	A			WOOD/PT-2		1	PASSAGE
204/1	BATHROOM 204	2'-8"X6'-8"	1 3/8"	WOOD	A			WOOD/PT-2		1	PRIVACY
208/1	DECK 208	2'-6X6'-8"	1 3/8"	WOOD	A	FULL		WOOD/PT-2		1	KEYED
301/1	ENTRY/STAIRS 301	3'-0"X6'-8"	1 3/8"	STEEL	B		1 HR	WOOD/PT-2		1	KEYED, SELF CLOSING
302/1	BEDROOM 302	2'-6"X6'-8"	1 3/8"	WOOD	A			WOOD/PT-2		1	PRIVACY
302/2	BEDROOM 302	2'-6"X6'-8"	1 3/8"	WOOD	A			WOOD/PT-2		1	PASSAGE
303/1	BEDROOM 303	2'-6"X6'-8"	1 3/8"	WOOD	A			WOOD/PT-2		1	PRIVACY
303/2	BEDROOM 303	2'-6"X6'-8"	1 3/8"	WOOD	A			WOOD/PT-2		1	PASSAGE
304/1	BEDROOM 304	2'-8"X6'-8"	1 3/8"	WOOD	A			WOOD/PT-2		1	PRIVACY
307/1	DECK 307	2'-6X6'-8"	1 3/8"	WOOD	A	FULL		WOOD/PT-2		1	KEYED
308/1	DECK 308	3'-0X6'-8"	1 3/8"	WOOD	A	FULL		WOOD/PT-2		1	KEYED

INTERIOR DOOR HARDWARE SCHEDULE (BASIS FOR PRICING)

NO.	MANUFACTURER	MODEL/DESCRIPTION	NO./TRIM	FUNCTION	FINISH	REMARKS
1	SCHLAGE	-	-	-	-	

Lachman
Architects & Planners

Architecture
Planning
Preservation

165 State Street
Portland, Maine 04101
207-773-3811

LICENSED ARCHITECT
DENIS LACHMAN
NO. 2691
STATE OF MAINE

ALTERATIONS TO
52 MONUMENT STREET
PORTLAND, MAINE

TITLE:
SCHEDULES
AND
ASSEMBLIES

DATE:
ORIGINAL: 11/05/13
REVISION 1: 12/10/13
REVISION 2:
REVISION 3:

ISSUED FOR:
CONSTRUCTION

DRAWING NO:
A5