P.T. 4x6 timber wall to retain exist. slope; stagger joints and secure with 12" galv. spikes

6x6 cedar posts, min. 2" thick lap joint w/ (4) galv 5.5" lag bolts

fabric-wrapped gravel and perf. pipe, tie into existing drainage

Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 06/10/13

Note: fasteners used to secure cedar posts to boards and 1x material are to be 2-1/4" SS trim screws

Macomber Residence St. Lawrence Street, Portland Maine

L-2

Date: 5-30-13
Scale: NTS
Drawing: Typical Cedar Fence Detail

peter burke landscape architecture
www.peterburkedesign.com
207-632-7372