

LED wall luminaires with directed light

Housing: One piece die-cast aluminum for direct attachment to a BEGA 19544 small opening wiring box. Die castings are marine grade, copper free ($\leq 0.3\%$ copper content) A360.0 aluminum alloy.

Enclosure: One piece die-cast aluminum cover frame secured by a captive, stainless steel set screws threaded into a stainless steel insert. Matte safety glass. Fully gasketed for weather tight operation using a molded silicone rubber gasket.

Electrical: 2.2W LED luminaire, 3.7 total system watts, -30°C start temperature. Integral 120V through 277V electronic LED driver. LED module(s) are available from factory for easy replacement. Standard LED color temperature is 3000K with an >80 CRI. Available in 4000K (>80 CRI); add suffix K4 to order.

Note: LEDs supplied with luminaire. Due to the dynamic nature of LED technology, LED luminaire data on this sheet is subject to change at the discretion of BEGA-US. For the most current technical data, please refer to www.bega-us.com.

Finish: All BEGA standard finishes are polyester powder coat with minimum 3 mil thickness. Available in four standard BEGA colors: Black (BLK); White (WHT); Bronze (BRZ); Silver (SLV). To specify, add appropriate suffix to catalog number. Custom colors supplied on special order.


CSA certified to U.S. and Canadian standards, suitable for wet locations. Protection class IP64

Weight: 0.5 lbs.

Luminaire Lumens: 128

Tested in accordance with LM-79-08

Type:
 BEGA Product:
 Project:
 Voltage:
 Color:
 Options:
 Modified:



	Lamps	A	B	C	Wiring box*
33513*	ADA 2.2W LED	2 $\frac{1}{8}$	5 $\frac{1}{2}$	2 $\frac{3}{8}$	19544

* Small opening wiring box included.

BEGA-US 1000 BEGA Way, Carpinteria, CA 93013 (805) 684-0533 FAX (805) 566-9474 www.bega-us.com

©copyright BEGA-US 2016 Updated 05/16