

DISPLAY THIS CARD ON PRINCIPAL FRONTAGE OF WORK



CITY OF PORTLAND BUILDING PERMIT



This is to certify that

WHELAN THOMAS C TRUSTEE

Located at

28 WATERVILLE ST

PERMIT ID: 2017-00227

ISSUE DATE: 03/09/2017

CBL: 017 E034001

has permission to **Creating new bathroom and closet on second floor within existing shell.**
provided that the person or persons, firm or corporation accepting this permit shall comply with all of the provisions of the Statues of Maine and of the Ordinances of the City of Portland regulating the construction, maintenance and use of the buildings and structures, and of the application on file in the department.

Notification of inspection and written permission procured before this building or part thereof is lathed or otherwise closed-in. 48 hour notice is required.

A final inspection must be completed before this building or part thereof is occupied. If a certificate of occupancy is required, it must be procured prior to occupancy.

N/A

/s/ Michael Russell, MS, Director

Fire Official

Building Official

**THIS CARD MUST BE POSTED ON THE STREET SIDE OF THE PROPERTY
THERE IS A PENALTY FOR REMOVING THIS CARD**

Approved Property Use - Zoning

Building Inspections

Fire Department

BUILDING PERMIT INSPECTION PROCEDURES
Please call 874-8703
or email: buildinginspections@portlandmaine.gov

**Check the Status of Permit or Schedule an Inspection at
<http://www.portlandmaine.gov/planning/permitstatus.asp>**

With the issuance of this permit, the owner, builder or their designee is required to provide adequate notice to the City of Portland Inspections Division for the inspections listed below. Appointments must be requested 48 to 72 hours in advance. The inspection date will need to be confirmed by this office.

- **Please read the conditions of approval that are attached to this permit.**
- **Permits expire in 6 months if the project is not started or ceases for 6 months.**
- **If the inspection requirements below are not followed, then additional fees may be incurred due to the issuance of a "Stop Work Order" and subsequent release to continue.**
- **Per Section 107.3.1 of the Maine Uniform Building and Energy Code (MUBEC), one set of printed approved stamped construction documents will be kept at the site of work and open to inspection by building officials.**

REQUIRED INSPECTIONS:

Close-in Plumbing/Framing

Electrical Close-in

Final - Electric

Final - Fire

Final Inspection

The project cannot move to the next phase prior to the required inspection and approval to continue.

If the permit requires a certificate of occupancy, it must be paid and issued to the owner or designee before the space may be occupied.

City of Portland, Maine - Building or Use Permit		Permit No: 2017-00227	Date Applied For: 02/23/2017	CBL: 017 E034001
389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716				
Proposed Use: Single family home	Proposed Project Description: Creating new bathroom and closet on second floor within existing shell.			
Dept: Fast Track Status: Approved w/Conditions Reviewer: Jeanie Bourke Approval Date: 03/09/2017 Note: Ok to Issue: <input checked="" type="checkbox"/> Conditions: <ol style="list-style-type: none"> 1) Hardwired photoelectric interconnected battery backup smoke detectors shall be installed in all sleeping rooms, protecting outside these rooms, and on every level. The same is required for existing buildings undergoing alterations, hard wired to the electrical system. Interconnection is required, where permanent wiring is feasible, which shall be verified upon inspection. 2) The review of this permit did not include a review or confirmation of the zoning legal use. It is only approving the specific work described in the plans and forms submitted. The current use of the property may be found to be unlawful. 3) Separate permits are required for any electrical, plumbing, sprinkler, fire alarm, HVAC systems, heating appliances, including pellet/wood stoves, commercial hood exhaust systems, fire suppression and fuel tanks. Separate plans may need to be submitted for approval as a part of this process. 4) Per the 2009 IRC Sec. R305 and the 2015 UPC plumbing code, bathrooms shall have a ceiling height of 6'-8" at the center of the front clearance (24") at the sink and toilet and at the showerhead above a minimum area of 30"x30". 5) Carbon Monoxide Alarms: Where required in existing dwellings. Where work requiring a permit occurs in existing dwellings that have attached garages or in existing dwellings within which fuel-fired appliances exist, carbon monoxide alarms shall be provided in accordance with Section R315.1. 6) This permit is being approved on the basis of plans submitted. Any deviations shall require a separate approval before starting that work. 				