

Fire ratings are available in most JELD-WEN® door product lines. There may be restrictions based on size and regional availability, so please use this sheet as a reference and discuss further with your JELD-WEN supplier. All door slabs must be used with fire-rated door systems for true fire protection. A door system consists of the door slab, frame, hardware and components.

Exterior Doors				
Product Type	Ratings	Models	Largest Slab Size	
Custom Wood Doors	20-minutes	<ul style="list-style-type: none"> • Fire-rated solid core • 1-3/4" to 2-1/4" doors 	Available with all-panel doors Radius top doors up to 60 minutes	4'0" x 8'0" Single* 7'0" x 8'0" Pair*
	45-minutes	<ul style="list-style-type: none"> • FyreWerks core • 1-3/4" to 2-1/4" doors 	Segment top doors up to 90 minutes	
	60-minutes	<ul style="list-style-type: none"> • FyreWerks core • 1-3/4" to 2-1/4" doors 	Select 20 and 45 minute doors available with glass (Custom quoted)	
	90-minutes	<ul style="list-style-type: none"> • FyreWerks core • 1-3/4" to 2-1/4" doors 		
Fiberglass Doors	20-minutes	<ul style="list-style-type: none"> • Fire-rated solid core • 1-3/4" doors • Laminated Veneer Lumber (LVL) stiles & rails • LFI-capped top rail and PVC capped stiles and bottom rails 	Available with all-panel doors Architectural Fiberglass Doors Design-Pro Fiberglass Doors Smooth-Pro Fiberglass Doors	3'0" x 8'0" Single 6'0" x 6'8" Pair
Engineered Composite	20-minutes	<ul style="list-style-type: none"> • Fire-rated core • 1-3/4" doors • AuraLast® Stiles 	FiberLast® Engineered Composite all-panel doors	3'0" x 8'0" Single 6'0" x 8'0" Pair
Steel Doors	20-minutes	<ul style="list-style-type: none"> • Wood edge 	Available with all-panel doors Contours™	3'0" x 6'8" Single 3'0" x 8'0" Single 6'0" x 7'0" Pair
	90-minutes	<ul style="list-style-type: none"> • Steel edge 	Energy Saver® Craftsman™ 2-Panel Designs	

Interior Doors				
Product Type	Ratings	Models	Largest Slab Size	
Custom Wood Doors	20-minutes	<ul style="list-style-type: none"> • Fire-rated solid core • 1-3/4" to 2-1/4" doors 	Available with all-panel doors Radius top doors up to 60 minutes	4'0" x 8'0" Single* 7'0" x 8'0" Pair*
	45-minutes	<ul style="list-style-type: none"> • FyreWerks core • 1-3/4" to 2-1/4" doors 	Segment top doors up to 90 minutes	
	60-minutes	<ul style="list-style-type: none"> • FyreWerks core • 1-3/4" to 2-1/4" doors 	Select 20 and 45 minute doors available with glass (Custom quoted)	
	90-minutes	<ul style="list-style-type: none"> • FyreWerks core • 1-3/4" to 2-1/4" doors 		
Custom Carved Doors	20-minutes	<ul style="list-style-type: none"> • Fire-rated solid core • 1-3/4" doors 	Available with all raised panel doors	3'0" x 8'0" Single
Molded Doors	20-minutes	<ul style="list-style-type: none"> • Wood-based panel core • 1-3/4" doors 	Available in all standard models except Impression™ Series doors	3'0" x 8'0" Single
	45-minutes	<ul style="list-style-type: none"> • Solid mineral core • 1-3/4" doors 	Craftsman III™ and Madison doors available with 20-minute fire rating only	
	60-minutes	<ul style="list-style-type: none"> • Solid mineral core • 1-3/4" doors 		
Flush Doors	20-minutes	<ul style="list-style-type: none"> • Wood-based panel core • 1-3/4" doors 	Available in all models	4'0" x 8'0" Single
	45-minutes	<ul style="list-style-type: none"> • Wood-based panel core or mineral core • 1-3/4" doors 		
	60-minutes	<ul style="list-style-type: none"> • Wood-based panel core or mineral core • 1-3/4" doors 		
	90-minutes	<ul style="list-style-type: none"> • Solid mineral core • 1-3/4" doors 		

*Size limitations for Custom Wood fire rated doors in fire rated wood jamb: 20-minute: 3'6" x 8'0" single, 5'6" x 8'0" pair | 45/60/90-minute: 3'6" x 8'0" single